

29 Dec 93

APPENDIX C
ARCHITECTURAL ESTIMATES

DISTRIBUTION STATEMENT A

Approved for public release;

Distribution Unlimited

933702




DEPARTMENT OF THE ARMY
CONSTRUCTION ENGINEERING RESEARCH LABORATORIES, CORPS OF ENGINEERS
P.O. BOX 9005
CHAMPAIGN, ILLINOIS 61826-9005

REPLY TO
ATTENTION OF: TR-I Library

17 Sep 1997

Based on SOW, these Energy Studies are unclassified/unlimited.
Distribution A. Approved for public release.


Marie Wakefield,
Librarian Engineering

Building 001

Architectural Estimate

THIS QUALITY INSPECTION

19971017 206

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. <u>1</u>		Building Name: <u>QUARTERS 1</u>	
Date Prepared: <u>29 DEC. 93</u>	Estimator: <u>K. STICK</u>	Sheet <u>1</u> of <u>2</u>	
BID ITEM - WALL / ROOF INSULATION			
Description	Quantity	Unit Measurement	
DIV. 02 REMOVAL & RESETTING OF			
EXIST. MILLWORK (BASE MOULDING)	729	L.F.	
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD.			
R=14.3 (WALL INSUL.)	5930	S.F.	
DIV. 07 07310 1017 INSTALL 6" UNFACED			
FIBERGLASS INSUL. R=19.0 (ROOF INSUL.)	3659	S.F.	
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL ON			
'Z' FURRING OVER 2" RIGID INSUL.	5930	S.F.	
(INCLUDE 4001)			
DIV. 09 INSTALL STD. 2" 'Z' FURRING @			
24" O.C. BETWEEN 2" RIGID INSUL.	38.9	C.L.F.	
DIV. 09 09920 1221 PAINTING 1/2" DRYWALL	5930	S.F.	
DIV. 16 ELEC. WORK ON OUTLETS / SWITCHES	58	EA.	
DIV. 16 ELEC. WORK ON WALL MTD.			
LIGHT FIXTURES	17	EA.	

Thu 30 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB0011: CB BLDG 001, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:37:27

TITLE PAGE 1

CB BLDG 001, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 001, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 12/30/93

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 30 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB0011: CB BLDG 001, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:37:27

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

		AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
01 General Contractor											
OVERHEAD	S		5.00	5.00							
HOME OFC	P		10.00								
PROFIT	S		8.66	5.00							
BOND	P		2.00								
02 Electrical Contractor											
OVERHEAD	P		5.00								
HOME OFC	P		10.00								
PROFIT	C		8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P		2.00								

Thu 30 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB0011: CB BLDG 001, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:37:27

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract,.....	1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 30 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB0011: CB BLDG 001, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:37:27

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	21,790	0	1,090	0	22,880	22879.54
CB BLDG 001, ECO #1	1.00 EA	21,790	0	1,090	0	22,880	22879.54

Thu 30 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB0011: CB BLDG 001, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:37:27

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	350	11,838	111	5,073	0	17,022	17021.89
CB BLDG 001, ECO #1 OVERHEAD	1.00	EA	350	11,838	111	5,073	0	17,022 851	17021.89
SUBTOTAL								17,873	
HOME OFC								1,787	
SUBTOTAL								19,660	
PROFIT								1,703	
SUBTOTAL								21,363	
BOND								427	
TOTAL INCL INDIRECTS								21,790	
CONTINGENCY								1,090	
TOTAL INCL OWNER COSTS								22,880	

Thu 30 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB0011: CB BLDG 001, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:37:27

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	15,651	783	1,643	1,565	393	20,035	20035.48
EL Electrical Contractor	1,371	69	144	137	34	1,755	1754.56

Thu 30 Dec 1993

U.S. Army Corps of Engineers

TIME 14:37:27

PROJECT CB0011: CB BLDG 001, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

	QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract									
Remove & Reset Existing Millwork (Base Moulding)	729.00	LF	ULABF	0.03 24	0.95 693	0.01 5	0.00 0	0.00 0	0.96 698
2" Polyiso., R-13 Rigid Insul.	729.00	SF	ACARA	0.01 5	0.26 190	0.00 2	0.90 657	0.00 0	1.16 848
6" Unfaced Batt, R19 Fbgs Insul	3659.00	SF	ACARA	0.01 30	0.30 1,087	0.00 11	0.21 776	0.00 0	0.51 1,874
1/2" Drywall, One Layer, One Face On Metal Studs or Furring, (13mm) For Taping, Spackling, And	5930.00	SF	ACARB	0.02 66 48	0.69 2,362 1,700	0.01 24 17	0.21 1,093 164	0.00 0	0.90 5,361
Std. 2" 'Z' Furring @ 24" O.C.	38.90	CLF	ACARA	2.09 81	74.50 2,898	0.72 28	28.09 1,093	0.00 0	103.31 4,019
Interior Roller Work One Coat Primer-Two Coats Paint	5930.00	SF	APTRA	0.01 64	0.29 1,701	0.00 19	0.19 1,131	0.00 0	0.48 2,852
Electrical Work on Outlets and Switches	58.00	EA	EELEB	0.28 16	11.00 638	0.04 2	2.12 123	0.00 0	13.16 763
Electrical Work on Wall Mtd. Light Fixtures	17.00	EA	EELEF	0.93 16	33.50 570	0.12 2	2.12 36	0.00 0	35.74 608
Contract				350	11,838	111	5,073	0	17,022
CB BLDG 001, ECO #1				350	11,838	111	5,073	0	17,022

Thu 30 Dec 1993

U.S. Army Corps of Engineers

TIME 14:37:27

PROJECT CB0011: CB BLDG 001, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. /	Building Name: <u>QUARTERS /</u>		
Date Prepared: <u>29 DEC. 93</u>	Estimator: <u>K. STICK</u>	Sheet <u>2</u> of <u>2</u>	

BID ITEM - WEATHERSTRIPPING / CAULKING

[illegible]

Thu 30 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB0013: CB BLDG 001, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 13:52:08

TITLE PAGE 1

CB BLDG 001, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 001, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 12/30/93

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 30 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB0013: CB BLDG 001, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 13:52:08

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

		AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
01 General Contractor											
OVERHEAD	P	5.00									
HOME OFC	P	10.00									
PROFIT	C	8.65			0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00									

Thu 30 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB0013: CB BLDG 001, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 13:52:08

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

*** END TABLE OF CONTENTS ***

Thu 30 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB0013: CB BLDG 001, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 13:52:08

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SION	TOTAL COST	UNIT COST
01 Contract	1.00 EA	3,346	0	167	0	3,513	3513.23
CB BLDG 001, ECO #3	1.00 EA	3,346	0	167	0	3,513	3513.23

Thu 30 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB0013: CB BLDG 001, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 13:52:08

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	65	2,330	18	266	0	2,614	2613.88
CB BLDG 001, ECO #3	1.00 EA	65	2,330	18	266	0	2,614	2613.88
OVERHEAD							131	
SUBTOTAL							2,745	
HOME OFC							274	
SUBTOTAL							3,019	
PROFIT							261	
SUBTOTAL							3,280	
BOND							66	
TOTAL INCL INDIRECTS							3,346	
CONTINGENCY							167	
TOTAL INCL OWNER COSTS							3,513	

Thu 30 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB0013: CB BLDG 001, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 13:52:08

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	2,614	131	274	261	66	3,346	3345.93

Thu 30 Dec 1993

U.S. Army Corps of Engineers

TIME 13:52:08

PROJECT CB0013: CB BLDG 001, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY UOM CREW ID			MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract								
Polyurethane Cmpd, 1/4"x1/4" Joint			4.65	166.39	1.03	9.54	0.00	176.96
Caulking of Exterior Doors and Windows	8.52	CLF ARFCA	40	1,418	9	81	0	1,508
Mtl Weatherstrip w/Neoprene Bulb For Head and Jamb	225.00	LF ACARB	0.07 17	2.62 590	0.03 6	0.66 148	0.00 0	3.31 744
Mtl Weatherstrip for Door Bottom Surface Mounted w/Vinyl Bulb	43.00	LF ACARB	0.21 9	7.50 322	0.08 3	0.85 36	0.00 0	8.42 362
Contract			65	2,330	18	266	0	2,614
CB BLDG 001, ECO #3			65	2,330	18	266	0	2,614

Thu 30 Dec 1993

U.S. Army Corps of Engineers

TIME 13:52:08

PROJECT CB0013: CB BLDG 001, ECO #3 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 002

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 2		Building Name: QUARTERS 2	
Date Prepared: 29 DEC. 93	Estimator: K. STICK	Sheet 1 of 3	
BID ITEM - WALL / ROOF INSULATION			
Description	Quantity	Unit Measurement	
DIV. 02 REMOVAL & RESETTING OF EXIST. MILLWORK (BASE & CASING)	1286	L.F.	
DIV. 06 06111 4201 2x4 WOOD FRAMING AROUND WINDOW & DOOR OPENINGS	640	B.F.	
DIV. 06 1x3 PINE JAMB EXTENSIONS	956	L.F.	
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD. R=14.3 (WALL INSUL.)	2898	S.F.	
DIV. 07 07210 1003 INSTALL 4" KRAFT FACED FIBERGLASS INSUL. R=11.0 (WALL INSUL.)	74	S.F.	
DIV. 02 REMOVE / RESET BASE CABINET (LIBRARY RM.)	40	L.F.	
DIV. 02 REMOVE EXIST. DRYWALL / BATT INSUL. (LIBRARY RM.)	122	S.F.	
DIV. 07 07210 1017 INSTALL 6" UNFACED FIBERGLASS INSUL. R=19.0 (ROOF INSUL. - MAIN HOUSE)	3026	S.F.	

[illegible]

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB0021: CB BLDG 002, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 14:43:27

TITLE PAGE 1

CB BLDG 002, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 002, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 05/17/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB0021: CB BLDG 002, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 14:43:27

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

		AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
01 General Contractor											
OVERHEAD	S		5.00	5.00							
HOME OFC	P		10.00								
PROFIT	S		8.66	5.00							
BOND	P		2.00								
02 Electrical Contractor											
OVERHEAD	P		5.00								
HOME OFC	P		10.00								
PROFIT	C		8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P		2.00								

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 14:43:27

PROJECT CB0021: CB BLDG 002, ECO #1 - ESOS Carlisle Barracks

TABLE OF CONTENTS

PREFINAL SUBMISSION

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB0021: CB BLDG 002, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:43:27

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SION	TOTAL COST	UNIT COST
01 Contract	1.00	EA	19,894	0	995	0	20,889	20888.67
CB BLDG 002, ECO #1	1.00	EA	19,894	0	995	0	20,889	20888.67

Tue 17 May 1994

U.S. Army Corps of Engineers
 PROJECT CB0021: CB BLDG 002, ECO #1 - ESOS Carlisle Barracks
 PREFINAL SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:43:27

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	292	9,622	99	5,847	0	15,568	15567.50
CB BLDG 002, ECO #1 OVERHEAD	1.00 EA	292	9,622	99	5,847	0	15,568	15567.50
							772	
SUBTOTAL							16,340	
HOME OFC							1,622	
SUBTOTAL							17,961	
PROFIT							1,545	
SUBTOTAL							19,506	
BOND							388	
TOTAL INCL INDIRECTS							19,894	
CONTNGENCY							995	
TOTAL INCL OWNER COSTS							20,889	

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB0021: CB BLDG 002, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:43:27

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
<<< Non-Contracted Work >>>	123	0	0	0	0	123	122.63
GC General Contractor	15,445	772	1,622	1,545	388	19,771	19771.34

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 14:43:27

PROJECT CB0021: CB BLDG 002, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

PREFINAL SUBMISSION

DETAIL PAGE 1

01. Contract

		QUANTY	UOM	CREW	ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract											
Removal & Resetting of Millwork						0.03	0.95	0.01	0.00	0.00	0.96
	1286.00	LF	ULABF			42	1,222	9	0	0	1,231
Sills & Plates, 2x4 So Yel Pine						0.02	0.80	0.02	0.24	0.00	1.06
Around Window & Door Openings	640.00	BF	ACARD			14	512	13	156	0	681
Jamb Extensions						0.03	0.79	0.01	0.42	0.00	1.22
	956.00	LF	ULABF			26	755	6	405	0	1,166
2" Polyiso, R 14.3, Rigid Insul.						0.01	0.26	0.00	0.90	0.00	1.16
	2898.00	SF	ACARA			21	753	7	2,611	0	3,372
4" Kraft Faced, R11 Fbgs Insul						0.01	0.30	0.00	0.14	0.00	0.44
	74.00	SF	ACARA			1	22	0	10	0	32
Remove & Reset Base Cabinets						0.21	7.60	0.08	0.00	0.00	7.68
	40.00	LF	ACARB			9	304	3	0	0	307
Remove Drywall/Batt Insulation						0.01	0.17	0.00	0.00	0.00	0.17
	122.00	SF	ULABF			1	21	0	0	0	21
6" Unfaced Batt, R19 Fbgs Insul						0.01	0.30	0.00	0.21	0.00	0.51
Roof Insulation	3026.00	SF	ACARA			25	899	9	642	0	1,549
1/2" Drywall, One Layer, One Face						0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)	3026.00	SF	ACARB			34	1,214	12	558	0	2,751
For Taping, Spackling, And						25	874	9	84		
Std 2" Z Furring, Galv.						2.09	74.50	0.72	28.09	0.00	103.31
	26.29	CLF	ACARA			55	1,959	19	738	0	2,716
Interior Roller Work						0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint	3026.00	SF	APTRA			33	868	10	577	0	1,455
4" Unfaced Batt, R11 Fbgs Insul						0.01	0.30	0.00	0.20	0.00	0.50
Roof Insulation (2nd Floor	325.00	SF	ACARA			3	97	1	65	0	163
Porch)											
Lead Paint Abatement						0.03	1.00	0.01	0.00	0.00	1.01
	122.00	SF	ULABB			4	122	1	0	0	123
Contract						292	9,622	99	5,847	0	15,568
BLDG 002, ECO #1						292	9,622	99	5,847	0	15,568

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 14:43:27

PROJECT CB0021: CB BLDG 002, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

[illegible]

Mon 03 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0023: CB BLDG 002, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:08:20

TITLE PAGE 1

CB BLDG 002, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 002, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/03/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

CREW ID: NAT92B UPB ID: NAT92A

TIME 14:08:20

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

01 General Contractor

OVERHEAD	P	5.00							
HOME OFC	P	10.00							
PROFIT	C	8.65	0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00							

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:08:20

PROJECT CB0023: CB BLDG 002, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....1
PROJECT DIRECT SUMMARY - LEVEL 1.....2
CONTRACTOR INDIRECT SUMMARY.....3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:08:20

PROJECT CB0023: CB BLDG 002, ECO #3 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 1

** PROJECT OWNER SUMMARY - LEVEL 1 **

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	3,138	0	157	0	3,295	3295.02
CB BLDG 002, ECO #3	1.00 EA	3,138	0	157	0	3,295	3295.02

CREW ID: NAT92B UPB ID: NAT92A

**** PROJECT DIRECT SUMMARY - LEVEL 1 ****

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
<hr/>								
01 Contract	1.00 EA	62	2,215	16	220	0	2,452	2451.53
							<hr/>	
CB BLDG 002, ECO #3 OVERHEAD	1.00 EA	62	2,215	16	220	0	2,452	2451.53
							123	
							<hr/>	
SUBTOTAL							2,574	
HOME OFC							257	
							<hr/>	
SUBTOTAL							2,832	
PROFIT							245	
							<hr/>	
SUBTOTAL							3,077	
BOND							62	
							<hr/>	
TOTAL INCL INDIRECTS							3,138	
CONTINGENCY							157	
							<hr/>	
TOTAL INCL OWNER COSTS							3,295	

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:08:20

PROJECT CB0023: CB BLDG 002, ECO #3 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 3

** CONTRACTOR INDIRECT SUMMARY **

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	2,452	123	257	245	62	3,138	3138.11

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:08:20

PROJECT CB0023: CB BLDG 002, ECO #3 - ESOS Carlisle Barracks

LED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY UOM		CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract								
Polyurethane Compd, 1/4"x1/4" Joint			4.65	166.39	1.03	9.54	0.00	176.96
Ext. Doors & Windows	9.56	CLF ARFCA	44	1,591	10	91	0	1,692
Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	161.00	LF ACARB	12	422	4	106	0	532
Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	27.00	LF ACARB	6	202	2	23	0	227
Bulb								
Contract			62	2,215	16	220	0	2,452
CB BLDG 002, ECO #3			62	2,215	16	220	0	2,452

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:08:20

PROJECT CB0023: CB BLDG 002, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 003

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 3

Building Name: QUARTERS 3

Date Prepared: 29

Estimator: K. STICK

Sheet 1 of 1

<p align="center">BID ITEM - WEATHERSTRIPPING / CAULK</p>	
--	--

[illegible]

Mon 03 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0033: CB BLDG 003, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:13:00

TITLE PAGE 1

CB BLDG 003, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 003, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/03/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:13:00

PROJECT CB0033: CB BLDG 003, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
--------	-----	-------	------	------	------	--------	--------	--------	--------

01 General Contractor

OVERHEAD	P	5.00							
HOME OFC	P	10.00							
PROFIT	C	8.65	0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00							

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:13:00

PROJECT CB0033: CB BLDG 003, ECO #3 - ESOS Carlisle Barracks

INTERIM SUBMISSION

CONTENTS PAGE 1

OF CONTENTS

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

*** END TABLE OF CONTENTS ***

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:13:00

PROJECT CB0033: CB BLDG 003, ECO #3 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 1

** PROJECT OWNER SUMMARY - LEVEL 1 **

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	629	0	31	0	660	659.96
CB BLDG 003, ECO #3	1.00 EA	629	0	31	0	660	659.96

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:13:00

PROJECT CB0033: CB BLDG 003, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

SUMMARY PAGE 3

** CONTRACTOR INDIRECT SUMMARY **

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	491	25	52	49	12	629	628.54

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:13:00

PROJECT CB0033: CB BLDG 003, ECO #3 - ESOS Carlisle Barracks

LED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

Polyurethane Cmpd, 1/4"x1/4"Joint			4.65	166.39	1.03	9.54	0.00	176.96
Exterior Door	0.17 CLF	ARFCA	1	28	0	2	0	30

Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	91.00 LF	ACARB	7	239	2	60	0	301

Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	19.00 LF	ACARB	4	142	1	16	0	160
Bulb								

Contract			11	409	4	78	0	491
----------	--	--	----	-----	---	----	---	-----

CB BLDG 003, ECO #3			11	409	4	78	0	491
---------------------	--	--	----	-----	---	----	---	-----

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:13:00

PROJECT CB0033: CB BLDG 003, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 004

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 4	Building Name: QUARTERS 4	
Date Prepared: 3 JAN 94	Estimator: K. STICK	Sheet 1 of 2
BID ITEM - WALL / ROOF INSULATION		
Description	Quantity	Unit Measurement
DIV. 02 REMOVAL & RESETTING OF EXIST. MILLWORK (BASE & CASING)	786	L.F.
DIV. 06 061114201 2x4 WOOD FRAMING AROUND WINDOW & DOOR OPENINGS	350	B.F.
DIV. 06 1x3 PINE JAMB EXTENSIONS	526	L.F.
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD. R=14.3 (WALL INSUL.)	1901	S.F.
DIV. 09 09200 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	1901	S.F.
DIV. 09 INSTALL STD. 2" 'Z' FURRING @ 24" O.C. BETWEEN 2" RIGID INSUL. BD.	13.86	C.L.F.
DIV. 09 09930 1221 PAINTING 1/2" DRYWALL	1901	S.F.

Mon 03 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0041: CB BLDG 004, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:28:39

TITLE PAGE 1

CB BLDG 004, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 004, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/03/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:28:39

PROJECT CB0041: CB BLDG 004, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
--------	-----	-------	------	------	------	--------	--------	--------	--------

01 General Contractor

OVERHEAD	S	5.00	5.00						
HOME OFC	P	10.00							
PROFIT	S	8.66	5.00						
BOND	P	2.00							

02 Electrical Contractor

OVERHEAD	P	5.00							
HOME OFC	P	10.00							
PROFIT	C	8.66	0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00							

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:28:39

PROJECT CB0041: CB BLDG 004, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

CONTENTS PAGE 1

OF CONTENTS

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....1
PROJECT DIRECT SUMMARY - LEVEL 1.....2
CONTRACTOR INDIRECT SUMMARY.....3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:28:39

PROJECT CB0041: CB BLDG 004, ECO #1 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 1

** PROJECT OWNER SUMMARY - LEVEL 1 **

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	17,071	0	854	0	17,924	17924.26
CB BLDG 004, ECO #1	1.00 EA	17,071	0	854	0	17,924	17924.26

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:28:39

PROJECT CB0041: CB BLDG 004, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

INTERIM SUBMISSION

SUMMARY PAGE 2

PROJECT DIRECT SUMMARY - LEVEL 1

[illegible]

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:28:39

PROJECT CB0041: CB BLDG 004, ECO #1 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 3

** CONTRACTOR INDIRECT SUMMARY **

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	13,335	667	1,400	1,334	335	17,071	17070.72

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:28:39

PROJECT CB0041: CB BLDG 004, ECO #1 - ESOS Carlisle Barracks

LED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

		QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Removal & Ressetting of Base & Casing	786.00	LF	ACARB	0.21 168	7.60 5,974	0.08 61	0.00 0	0.00 0		7.68 6,035
Sills & Plates, 2x4 So Yel Pine Around Doors & Windows	350.00	BF	ACARD	0.02 8	0.80 280	0.02 7	0.24 85	0.00 0		1.06 372
Jamb Extensions	526.00	LF	ULABF	0.03 14	0.79 416	0.01 3	0.42 223	0.00 0		1.22 642
2" Polyiso, R14.3, Rigid Insul.	1901.00	SF	ACARA	0.01 14	0.26 494	0.00 5	0.90 1,713	0.00 0		1.16 2,212
1/2" Drywall, One Layer, One Face On Metal Studs or Furring, (13mm) For Taping, Spackling, And	1901.00	SF	ACARB	0.02 21 15	0.69 763 549	0.01 8 6	0.21 350 53	0.00 0		0.91 1,728
Std 2" Z Furring, Galv.	13.86	CLF	ACARA	2.09 29	74.50 1,033	0.72 10	28.09 389	0.00 0		103.31 1,432
Interior Roller Work One Coat Primer-Two Coats Paint	1901.00	SF	APTRA	0.01 20	0.29 545	0.00 6	0.19 363	0.00 0		0.48 914
Contract				290	10,053	106	3,176	0		13,335
CB BLDG 004, ECO #1				290	10,053	106	3,176	0		13,335

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:28:39

PROJECT CB0041: CB BLDG 004, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 4

Building Name: QUARTERS 4

Date Prepared: 3 JAN 94

Estimator: K. STICK

Sheet 2 of 2

<p align="center">BID ITEM - WEATHERSTRIPPING /CAULK</p>	
---	--

[illegible]

Mon 03 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0043: CB BLDG 004, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:32:04

TITLE PAGE 1

CB BLDG 004, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 004, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/03/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:32:04

PROJECT CB0043: CB BLDG 004, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
--------	-----	-------	------	------	------	--------	--------	--------	--------

01 General Contractor

OVERHEAD	P	5.00							
HOME OFC	P	10.00							
PROFIT	C	8.65	0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00							

LABOR ID: R01_92

EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B

UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:32:04

PROJECT CB0043: CB BLDG 004, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....1
PROJECT DIRECT SUMMARY - LEVEL 1.....2
CONTRACTOR INDIRECT SUMMARY.....3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:32:04

PROJECT CB0043: CB BLDG 004, ECO #3 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 1

** PROJECT OWNER SUMMARY - LEVEL 1 **

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	1,504	0	75	0	1,580	1579.63
CB BLDG 004, ECO #3	1.00 EA	1,504	0	75	0	1,580	1579.63

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:32:04

PROJECT CB0043: CB BLDG 004, ECO #3 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 3

** CONTRACTOR INDIRECT SUMMARY **

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	1,175	59	123	117	29	1,504	1504.41

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:32:04

PROJECT CB0043: CB BLDG 004, ECO #3 - ESOS Carlisle Barracks

LED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTITY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
----------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

Polyurethane Cmpd, 1/4"x1/4" Joint			4.65	166.39	1.03	9.54	0.00	176.96
Exterior Doors & Windows	5.26	CLF ARFCA	24	875	5	50	0	931

Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	51.00	LF ACARB	4	134	1	34	0	169

Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	9.00	LF ACARB	2	67	1	8	0	76
Bulb								

Contract			30	1,076	8	91	0	1,175
----------	--	--	----	-------	---	----	---	-------

CB BLDG 004, ECO #3			30	1,076	8	91	0	1,175
---------------------	--	--	----	-------	---	----	---	-------

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 14:32:04

PROJECT CB0043: CB BLDG 004, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 005
(Typical for 006, 017, 018, 019,
020, 021, 026, and 029)

Architectural Estimate

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 5		Building Name: QUARTERS 5	
Date Prepared: 5 JAN. 94	Estimator: K. STICK	Sheet 1 of 2	
BID ITEM - WALL / ROOF INSUL.			
Description	Quantity	Unit Measurement	
DIV. 02 REMOVAL & RESETTING OF EXIST'G MILLWORK (BASE & CASING)	1536	L.F.	
DIV. 06 061114201 2x4 WOOD FRAMING AROUND WINDOW & DOOR OPENINGS	720	B.F.	
DIV. 06 1x3 PINE JAMB EXTENSIONS	1078	L.F.	
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD. R = 14.3 (WALL INSUL.)	3212	S.F.	
DIV. 07 07210 1017 INSTALL 6" UNFACED FIBERGLASS INSUL. R=19.0 (ROOF INSUL.)	2332	S.F.	
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	3212	S.F.	
DIV. 09 INSTALL STD. 2" 'Z' FURRING @ 24" O.C. BETWEEN 2" RIGID INSUL. BD.	21.6	C.L.F.	
DIV. 09 09920 1221 PAINTING 1/2" DRYWALL	3212	S.F.	
DIV. 16 ELEC. WORK ON OUTLETS & SWITCHES	40	EA.	

*** NOTE :** QUANTITIES INCLUDE BOTH SIDES OF DBL. HOUSE.

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0051: CB BLDG 005, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 13:41:03

TITLE PAGE 1

CB BLDG 005, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 005, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/06/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0051: CB BLDG 005, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 13:41:03

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	S	5.00	5.00							
HOME OFC	P	10.00								
PROFIT	S	8.66	5.00							
BOND	P	2.00								

02 Electrical Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 13:41:03

PROJECT CB0051: CB BLDG 005, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

*** END TABLE OF CONTENTS ***

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0051: CB BLDG 005, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 13:41:03

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00	EA	20,104	0	1,005	0	21,109	21109.39
CB BLDG 005, ECO #1	1.00	EA	20,104	0	1,005	0	21,109	21109.39

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0051: CB BLDG 005, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 13:41:03

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	292	9,602	96	6,006	0	15,705	15704.90
CB BLDG 005, ECO #1 OVERHEAD	1.00 EA	292	9,602	96	6,006	0	15,705 785	15704.90
SUBTOTAL HOME OFC							16,490 1,649	
SUBTOTAL PROFIT							18,139 1,571	
SUBTOTAL BOND							19,710 394	
TOTAL INCL INDIRECTS CONTINGENCY							20,104 1,005	
TOTAL INCL OWNER COSTS							21,109	

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0051: CB BLDG 005, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 13:41:03

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	15,179	759	1,594	1,518	381	19,431	19430.58
EL Electrical Contractor	526	26	55	53	13	674	673.60

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 13:41:03

PROJECT CB0051: CB BLDG 005, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY UOM		CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract								
Removal & Resetting of Millwork			0.03	0.95	0.01	0.00	0.00	0.96
1536.00 LF	ULABF		50	1,459	11	0	0	1,470
Sills & Plates, 2x4 So Yel Pine			0.02	0.80	0.02	0.24	0.00	1.06
Around Window & Door Openings	720.00 BF	ACARB	16	576	14	176	0	766
Jamb Extensions			0.03	0.79	0.01	0.42	0.00	1.22
1078.00 LF	ULABF		29	852	6	457	0	1,315
2" Polyiso., R14.3 Rigid Insul.			0.01	0.26	0.00	0.90	0.00	1.16
3212.00 SF	ACARA		23	835	8	2,894	0	3,737
6" Unfaced Batt, R19 Fbgs Insul			0.01	0.30	0.00	0.21	0.00	0.51
2332.00 SF	ACARA		19	693	7	494	0	1,194
1/2" Drywall, One Layer, One Face			0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)	3212.00 SF	ACARB	36	1,289	13	592	0	2,920
For Taping, Spackling, And			26	928	10	89		
td. 2" Z Furring, Galv.			2.09	74.50	0.72	28.09	0.00	103.31
21.60 CLF	ACARA		45	1,609	16	607	0	2,232
Interior Roller Work			0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint	3212.00 SF	APTRA	35	921	10	613	0	1,545
Electrical Work on Outlets & Switches			0.28	11.00	0.04	2.12	0.00	13.16
40.00 EA	EELEB		11	440	1	85	0	526
Contract			292	9,602	96	6,006	0	15,705
CB BLDG 005, ECO #1			292	9,602	96	6,006	0	15,705

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 13:41:03

PROJECT CB0051: CB BLDG 005, ECO #1 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 5	Building Name: QUARTERS 5	
Date Prepared: 5 JAN. 94	Estimator: K. STICK	Sheet 2 of 2

<div style="text-align: right;"> BID ITEM - WEATHERSTRIPPING /CAULKING </div>	
--	--

[illegible]

*NOTE: QUANTITIES INCLUDE BOTH SIDES OF DBL. HOUSE.

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0053: CB BLDG 005, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 13:44:00

TITLE PAGE 1

CB BLDG 005, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 005, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/05/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0053: CB BLDG 005, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 13:44:00

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 13:44:00

PROJECT CB0053: CB BLDG 005, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....1
PROJECT DIRECT SUMMARY - LEVEL 1.....2
CONTRACTOR INDIRECT SUMMARY.....3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0053: CB BLDG 005, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 13:44:00

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	2,859	0	143	0	3,002	3002.07
CB BLDG 005, ECO #3	1.00 EA	2,859	0	143	0	3,002	3002.07

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	58	2,062	14	158	0	2,234	2233.57
CB BLDG 005, ECO #3 OVERHEAD	1.00	EA	58	2,062	14	158	0	2,234 112	2233.57
SUBTOTAL HOME OFC								<hr/> 2,345 235 <hr/>	
SUBTOTAL PROFIT								2,580 223 <hr/>	
SUBTOTAL BOND								2,803 56 <hr/>	
TOTAL INCL INDIRECTS CONTNGENCY								2,859 143 <hr/>	
TOTAL INCL OWNER COSTS								3,002	

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0053: CB BLDG 005, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 13:44:00

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	2,234	112	235	223	56	2,859	2859.11

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 13:44:00

PROJECT CB0053: CB BLDG 005, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

Polyurethane Cmpd, 1/4"x1/4" Joint			4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	10.78	CLF ARFCA	50	1,794	11	103	0	1,908

Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	68.00	LF ACARB	5	178	2	45	0	225

Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	12.00	LF ACARB	3	90	1	10	0	101
Bulb								

Contract			58	2,062	14	158	0	2,234
----------	--	--	----	-------	----	-----	---	-------

CB BLDG 005, ECO #3			58	2,062	14	158	0	2,234
---------------------	--	--	----	-------	----	-----	---	-------

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 13:44:00

PROJECT CB0053: CB BLDG 005, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 023

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 23		Building Name: THORPE GYM	
Date Prepared: 3 JAN 94	Estimator: DJL	Sheet 1 of 3	
BID ITEM WALL / ROOF INSULATION			
Description	Quantity	Unit Measurement	
DIV. 06 0611 4201 2x4 WOOD FRAMING @ WINDOW & DOOR OPENINGS	1,055	B.F.	
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD. R= 14.3 (WALL INSUL)	10,318	S.F.	
DIV. 07 07210 1017 INSTALL 6" UNFACED FIBERGLASS INSUL R= 19.0 (ROOF INSUL.)	11,229	S.F.	
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	10,318	S.F.	
DIV. 09 INSTALL STD. 2" 'Z' FURRING @ 24" ON WALLS	71	C.L.F.	
DIV. 09 09920 1221 PAINTING 1/2" DRYWALL	10,318	S.F.	
DIV. 09 INSTALL 4" VINYL BASE	890	L.F.	
DIV. 16 ELECT. WORK ON OUTLETS & SWITCHES	22	EA.	

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 23

Building Name: THORPE GYM

Date Prepared: 3 JAN 94

Estimator: *DL*

Sheet 2 of 3

<div style="text-align: right;"> BID ITEM WALL / ROOF INSULATION </div>	
--	--

[illegible]

Mon 03 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0231: CB BLDG 023, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:09:31

TITLE PAGE 1

CB BLDG 023, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 023, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/03/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:09:31

PROJECT CB0231: CB BLDG 023, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
--------	-----	-------	------	------	------	--------	--------	--------	--------

01 General Contractor

OVERHEAD	S	5.00	5.00
HOME OFC	P	10.00	
PROFIT	S	8.66	5.00
BOND	P	2.00	

02 Electrical Contractor

OVERHEAD	P	5.00							
HOME OFC	P	10.00							
PROFIT	C	8.66	0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00							

LABOR ID: R01_92

EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B

UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:09:31

PROJECT CB0231: CB BLDG 023, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....1
PROJECT DIRECT SUMMARY - LEVEL 1.....2
CONTRACTOR INDIRECT SUMMARY.....3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:09:31

PROJECT CB0231: CB BLDG 023, ECO #1 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 1

** PROJECT OWNER SUMMARY - LEVEL 1 **

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	56,478	0	2,824	0	59,302	59301.71
CB BLDG 023, ECO #1	1.00 EA	56,478	0	2,824	0	59,302	59301.71

LABOR ID: R01 92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0231: CB BLDG 023, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 15:09:31

SUMMARY PAGE 2

[illegible]

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:09:31

PROJECT CB0231: CB BLDG 023, ECO #1 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 3

** CONTRACTOR INDIRECT SUMMARY **

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	41,760	2,088	4,385	4,177	1,048	53,459	53458.57
EL Electrical Contractor	2,359	118	248	236	59	3,019	3019.25

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:09:31

PROJECT CB0231: CB BLDG 023, ECO #1 - ESOS Carlisle Barracks

LED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

	QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract									
Sills & Plates, 2x4 So Yel Pine				0.02	0.80	0.02	0.24	0.00	1.06
	1055.00	BF	ACARD	24	844	21	257	0	1,122
2" Polyiso, R14.3, Rigid Insul.				0.01	0.26	0.00	0.90	0.00	1.16
	10318	SF	ACARA	75	2,683	26	9,297	0	12,005
6" Unfaced Batt, R19 Fbgs Insul				0.01	0.30	0.00	0.21	0.00	0.51
	11229	SF	ACARA	94	3,337	32	2,381	0	5,750
1/2" Drywall, One Layer, One Face				0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)	10318	SF	ACARB	116	4,139	43	1,902	0	9,380
For Taping, Spackling, And				84	2,980	31	285		
Std. 2" Z Furring, Galv.				2.09	74.50	0.72	28.09	0.00	103.31
	71.00	CLF	ACARA	148	5,290	51	1,994	0	7,335
Interior Roller Work				0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint	10318	SF	APTRA	111	2,960	33	1,969	0	4,962
4" Vinyl Base				0.02	0.61	0.00	0.74	0.00	1.36
	890.00	LF	APAPA	20	543	3	660	0	1,206
Electrical Work on Switches & Outlets				0.28	11.00	0.04	2.12	0.00	13.16
	22.00	EA	EELEB	6	242	1	47	0	289
Electrical Work on Exit Signs				0.82	32.50	0.11	2.12	0.00	34.73
	7.00	EA	EELEB	6	228	1	15	0	243
Electrical Work on Fire Alarm Pull Stations				0.82	32.50	0.11	2.12	0.00	34.73
	3.00	EA	EELEB	2	98	0	6	0	104
Electrical Work on Fire Alarm Bells				0.82	32.50	0.11	2.12	0.00	34.73
	2.00	EA	EELEB	2	65	0	4	0	69
Electrical Work on Wall Mounted Light Fixtures				1.05	41.50	0.13	2.12	0.00	43.75
	28.00	EA	EELEB	29	1,162	4	59	0	1,225
Electrical Work on 200A Disc. Switch				5.38	213.02	0.69	0.00	0.00	213.71
	2.00	EA	EELEB	11	426	1	0	0	427
Contract				728	24,996	246	18,877	0	44,119
CB BLDG 023, ECO #1				728	24,996	246	18,877	0	44,119

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:09:31

PROJECT CB0231: CB BLDG 023, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 23

Building Name: THORPE GYM

Date Prepared: 3 JAN. 94

Estimator: DJL

Sheet 3 of 3

BID ITEM	WEATHERSTRIPPING/CAULKING
----------	---------------------------

[illegible]

Mon 03 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0233: CB BLDG 023, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:12:07

TITLE PAGE 1

CB BLDG 023, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 023, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/03/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0233: CB BLDG 023, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:12:07

SETTINGS PAGE 1

**- CONTRACTOR SETTINGS **-

	AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON

01 General Contractor										
OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:12:07

PROJECT CB0233: CB BLDG 023, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....1
PROJECT DIRECT SUMMARY - LEVEL 1.....2
CONTRACTOR INDIRECT SUMMARY.....3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:12:07

PROJECT CB0233: CB BLDG 023, ECO #3 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 1

** PROJECT OWNER SUMMARY - LEVEL 1 **

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIQH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	4,176	0	209	0	4,385	4384.60
CB BLDG 023, ECO #3	1.00 EA	4,176	0	209	0	4,385	4384.60

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0233: CB BLDG 023, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 15:12:07

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	3,262	163	343	326	82	4,176	4175.81

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:12:07

PROJECT CB0233: CB BLDG 023, ECO #3 - ESOS Carlisle Barracks

LED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

Polyurethane Cmpd, 1/4"x1/4"Joint			4.65	166.39	1.03	9.54	0.00	176.96
Exterior Doors & Windows	13.83	CLF ARFCA	64	2,301	14	132	0	2,447
Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	170.00	LF ACARB	13	446	5	112	0	562
Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	30.00	LF ACARB	6	225	2	25	0	253
Bulb								

Contract

83	2,972	21	269	0	3,262
----	-------	----	-----	---	-------

CB BLDG 023, ECO #3

83	2,972	21	269	0	3,262
----	-------	----	-----	---	-------

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:12:07

PROJECT CB0233: CB BLDG 023, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 024

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 24

Building Name: COREN APARTMENTS

Date Prepared: 5 JAN. 94

Estimator: D. J. L.

Sheet / of /

BID ITEM	WEATHERSTRIPPING / CAULKING
----------	-----------------------------

[illegible]

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0243: CB BLDG 024, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 13:49:06

TITLE PAGE 1

CB BLDG 024, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 024, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/05/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0243: CB BLDG 024, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 13:49:06

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 13:49:06

PROJECT CB0243: CB BLDG 024, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0243: CB BLDG 024, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 13:49:06

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	5,626	0	281	0	5,907	5906.89
CB BLDG 024, ECO #3	1.00 EA	5,626	0	281	0	5,907	5906.89

Wed 05 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB0243: CB BLDG 024, ECO #3 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 13:49:06

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	112	3,990	29	376	0	4,395	4394.79
CB BLDG 024, ECO #3 OVERHEAD	1.00 EA	112	3,990	29	376	0	4,395 220	4394.79
SUBTOTAL HOME OFC							4,615 461	
SUBTOTAL PROFIT.							5,076 439	
SUBTOTAL BOND							5,515 110	
TOTAL INCL INDIRECTS CONTNGENCY							5,626 281	
TOTAL INCL OWNER COSTS							5,907	

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0243: CB BLDG 024, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 13:49:06

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	4,395	220	461	439	110	5,626	5625.61

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 13:49:06

PROJECT CB0243: CB BLDG 024, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract								
Polyurethane Cmpd, 1/4"x1/4" Joint			4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	17.86	CLF ARFCA	83	2,972	18	170	0	3,161
Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	251.00	LF ACARB	18	658	7	165	0	830
Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	48.00	LF ACARB	10	360	4	41	0	404
Bulb								
Contract			112	3,990	29	376	0	4,395
CB BLDG 024, ECO #3			112	3,990	29	376	0	4,395

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 13:49:06

PROJECT CB0243: CB BLDG 024, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 025

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 25	Building Name: QUARTERS 25	
Date Prepared: 3 JAN 94	Estimator: K. STICK	Sheet 1 of 3
BID ITEM - INSUL. GL. / DBL. HUNG WINDOWS		
Description	Quantity	Unit Measurement
REPLACE EXIST'G SINGLE GLAZED ALUM.		
WINDOWS w/ ANDERSEN PERMA-SHIELD WINDOWS		
w/ HIGH PERFORMANCE GLAZING w/SCREENS		
A (14) 2'-8" x 4'-4" OPENING		
B (2) 2'-4" x 4'-4" OPENING		
TOTAL 16 WINDOWS IN ALUM. SIDING		
DIV. 02 02112 1B11		
REMOVE EXIST'G WINDOWS @ ± 12 S.F. MAX. EA.	16	EA.
DIV. 08 NEW WINDOWS		
DBL. HUNG 2442	2	EA
DBL. HUNG 2842	14	EA.
AUXILLARY CASING 3/4" THK. x 3 1/2"		
HEAD & JAMBS		
(14) 10 L.F. = 140 L.F.		
(2) 9 L.F. = 18 L.F.		
158 L.F. TOTAL ≈	160	L.F.
TRIM OUT 16 WINDOWS - EXTENSION JAMBS, CASING		
STOOL & APRON	16	OPEN'G

[illegible]

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0252: CB BLDG 025, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:10:56

TITLE PAGE 1

CB BLDG 025, ECO #2
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 025, Windows
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/05/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0252: CB BLDG 025, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:10:56

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:10:56

PROJECT CB0252: CB BLDG 025, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0252: CB BLDG 025, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:10:56

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00	EA	12,147	0	607	0	12,754	12753.83
CB BLDG 025, ECO #2	1.00	EA	12,147	0	607	0	12,754	12753.83

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0252: CB BLDG 025, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:10:56

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	149	3,666	47	5,776	0	9,489	9488.98
CB BLDG 025, ECO #2 OVERHEAD	1.00 EA	149	3,666	47	5,776	0	9,489 474	9488.98
SUBTOTAL HOME OFC							9,963 996	
SUBTOTAL PROFIT.							10,960 949	
SUBTOTAL BOND							11,908 238	
TOTAL INCL INDIRECTS CONTNGENCY							12,147 607	
TOTAL INCL OWNER COSTS							12,754	

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0252: CB BLDG 025, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:10:56

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	9,489	474	996	949	238	12,147	12146.50

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:10:56

PROJECT CB0252: CB BLDG 025, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:10:56

PROJECT CB0252: CB BLDG 025, ECO #2 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

	QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract									
Demo Windows < 15 SF(1.3M2)				1.67	48.29	0.25	0.00	0.00	48.54
Wood or Metal Frames	16.00	EA	ULABB	27	773	4	0	0	777
Dbl. Hung 2442 Window				0.59	21.00	0.22	290.44	0.00	311.66
	2.00	EA	ACARB	1	42	0	581	0	623
Dbl. Hung 2842 Window				0.59	21.00	0.22	311.64	0.00	332.86
	14.00	EA	ACARB	8	294	3	4,363	0	4,660
Aux. Casing, Head & Jambs				0.25	0.00	0.09	3.71	0.00	3.80
	160.00	LF		40	0	14	594	0	608
Trim Out Windows				0.42	15.00	0.15	11.13	0.00	26.28
	16.00	EA	ACARB	7	240	2	178	0	421
Drywall Patching				0.56	19.95	0.19	0.29	0.00	20.43
	112.00	SF	ACARA	63	2,234	22	32	0	2,288
Paint Int Plaster-Drywall(Brush)				0.03	0.74	0.01	0.25	0.00	1.00
Seal Coat Primer-Three Coats Pnt	112.00	SF	APTRA	3	83	1	28	0	112
Contract				149	3,666	47	5,776	0	9,489
CB BLDG 025, ECO #2				149	3,666	47	5,776	0	9,489

[illegible]

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0253: CB BLDG 025, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:15:23

TITLE PAGE 1

CB BLDG 025, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 025, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/05/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0253: CB BLDG 025, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:15:23

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:15:23

PROJECT CB0253: CB BLDG 025, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0253: CB BLDG 025, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:15:23

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	793	0	40	0	833	832.68
CB BLDG 025, ECO #3	1.00 EA	793	0	40	0	833	832.68

Wed 05 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB0253: CB BLDG 025, ECO #3 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:15:23

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	16	563	4	52	0	620	619.52
CB BLDG 025, ECO #3	1.00 EA	16	563	4	52	0	620	619.52
OVERHEAD							31	
SUBTOTAL							650	
HOME OFC							65	
SUBTOTAL							716	
PROFIT.							62	
SUBTOTAL							777	
BOND							16	
TOTAL INCL INDIRECTS							793	
CONTINGENCY							40	
TOTAL INCL OWNER COSTS							833	

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0253: CB BLDG 025, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:15:23

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	620	31	65	62	16	793	793.03

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:15:23

PROJECT CB0253: CB BLDG 025, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

Polyurethane Cmpd, 1/4"x1/4" Joint			4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	2.58	CLF ARFCA	12	429	3	25	0	457

Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	34.00	LF ACARB	3	89	1	22	0	112

Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	6.00	LF ACARB	1	45	0	5	0	51
Bulb								

Contract			16	563	4	52	0	620
----------	--	--	----	-----	---	----	---	-----

CB BLDG 025, ECO #3			16	563	4	52	0	620
---------------------	--	--	----	-----	---	----	---	-----

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:15:23

PROJECT CB0253: CB BLDG 025, ECO #3 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 028

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 28		Building Name: QUARTERS 28	
Date Prepared: 6 JAN.94	Estimator: K. STICK		Sheet 1 of 3
BID ITEM - WALL / ROOF INSULATION			
Description	Quantity	Unit Measurement	
DIV. 02 REMOVAL & RESETTING OF EXISTG. MILLWORK (BASE & CASING)	856	L.F.	
DIV. 06 06111 4201 2x4 WOOD FRAMING AROUND WINDOW & DOOR OPENINGS	347	B.F.	
DIV. 06 1x3 PINE JAMB EXTENSIONS	520	L.F.	
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD. R = 14.3 (WALL INSUL.)	2244	S.F.	
DIV. 07 BLOWN-IN CELLULOSE INSUL. - 4" ± BETWEEN CEIL. JOISTS R = 11.0	1362	S.F.	
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	2244	S.F.	
DIV. 09 INSTALL STD. 2" 'Z' FURR'G @ 24" O.C. BETWEEN 2" RIGID INSUL. BD.	14.88	C.L.F.	
DIV. 09 09920 1221 PAINTG 1/2" DRYWALL	2244	S.F.	

[illegible]

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0281: CB BLDG 028, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:44:02

TITLE PAGE 1

CB BLDG 028, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 028, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/10/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0281: CB BLDG 028, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:44:02

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	S	5.00	5.00							
HOME OFC	P	10.00								
PROFIT	S	8.66	5.00							
BOND	P	2.00								

02 Electrical Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 14:44:02

PROJECT CB0281: CB BLDG 028, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0281: CB BLDG 028, ECO #1 - ESOS Carlisle Barracks

TIME 14:44:02

INTERIM SUBMISSION

SUMMARY PAGE 1

** PROJECT OWNER SUMMARY - LEVEL 1 **

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	13,197	0	660	0	13,857	13856.88
CB BLDG 028, ECO #1	1.00 EA	13,197	0	660	0	13,857	13856.88

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0281: CB BLDG 028, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:44:02

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	197	6,319	82	3,909	0	10,309	10309.19
CB BLDG 028, ECO #1 OVERHEAD	1.00 EA	197	6,319	82	3,909	0	10,309 515	10309.19
SUBTOTAL							10,825	
HOME OFC							1,082	
SUBTOTAL							11,907	
PROFIT							1,031	
SUBTOTAL							12,938	
BOND							259	
TOTAL INCL INDIRECTS							13,197	
CONTINGENCY							660	
TOTAL INCL OWNER COSTS							13,857	

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0281: CB BLDG 028, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:44:02

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	10,046	502	1,055	1,005	252	12,860	12860.23
EL Electrical Contractor	263	13	28	26	7	337	336.80

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 14:44:02

PROJECT CB0281: CB BLDG 028, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

		QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Removal & Resetting of Millwork					0.03	0.95	0.01	0.00	0.00	0.96
	856.00	LF	ULABF		28	813	6	0	0	819
Sills & Plates, 2x4 So Yel Pine					0.02	0.80	0.02	0.24	0.00	1.06
	347.00	BF	ACARD		8	278	7	85	0	369
Jamb Extensions					0.03	0.79	0.01	0.42	0.00	1.22
	520.00	LF	ULABF		14	411	3	220	0	634
2" Polyiso., R14.3 Rigid Insul.					0.01	0.26	0.00	0.90	0.00	1.16
	2244.00	SF	ACARA		16	583	6	2,022	0	2,611
Blown-in Cell. Insul. 4", R11.0					0.00	0.09	0.01	0.13	0.00	0.23
	1362.00	SF	AASBD		4	123	19	173	0	315
1/2" Drywall, One Layer, One Face					0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)					25	900	9	414	0	2,040
For Taping, Spackling, And					18	648	7	62		
td 2" Z Furring, Galv.					2.09	74.50	0.72	28.09	0.00	103.31
	14.88	CLF	ACARA		31	1,109	11	418	0	1,537
Interior Roller Work					0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint					24	644	7	428	0	1,079
Paint Int Wd Trim, 1Prime, 2Paint					0.04	1.14	0.01	0.08	0.00	1.23
Enamel Primer, Alkyd or Latex Pnt					22	590	7	44	0	641
Electrical Work on Outlets & Switches					0.28	11.00	0.04	2.12	0.00	13.16
	20.00	EA	EELEB		6	220	1	42	0	263
Contract					197	6,319	82	3,909	0	10,309
CB BLDG 028, ECO #1					197	6,319	82	3,909	0	10,309

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 14:44:02

PROJECT CB0281: CB BLDG 028, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

[illegible]

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0283: CB BLDG 028, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:48:20

TITLE PAGE 1

CB BLDG 028, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 028, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/10/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0283: CB BLDG 028, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:48:20

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0283: CB BLDG 028, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:48:20

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0283: CB BLDG 028, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:48:20

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SION	TOTAL COST	UNIT COST
01 Contract	1.00 EA	1,491	0	75	0	1,565	1565.36
CB BLDG 028, ECO #3	1.00 EA	1,491	0	75	0	1,565	1565.36

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0283: CB BLDG 028, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:48:20

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	30	1,066	7	91	0	1,165	1164.64
CB BLDG 028, ECO #3 OVERHEAD	1.00	EA	30	1,066	7	91	0	1,165 58	1164.64
SUBTOTAL HOME OFC								1,223 122	
SUBTOTAL PROFIT								1,345 116	
SUBTOTAL BOND								1,462 29	
TOTAL INCL INDIRECTS CONTINGENCY								1,491 75	
TOTAL INCL OWNER COSTS								1,565	

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0283: CB BLDG 028, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:48:20

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	1,165	58	122	116	29	1,491	1490.82

Mon 10 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB0283: CB BLDG 028, ECO #3 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 01. Contract

TIME 14:48:20

DETAILED ESTIMATE

DETAIL PAGE 1

QUANTY UOM CREW ID				MANERS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST

Contract									
Polyurethane Cmpd, 1/4"x1/4" Joint				4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	5.20	CLF	ARFCA	24	865	5	50	0	920
Mtl Weatherstrip w/Neoprene Bulb				0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	51.00	LF	ACARB	4	134	1	34	0	169
Mtl Weatherstrip for Door Bottom				0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	9.00	LF	ACARB	2	67	1	8	0	76
Bulb									

Contract				30	1,066	7	91	0	1,165

CB BLDG 028, ECO #3				30	1,066	7	91	0	1,165

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 14:48:20

PROJECT CB0283: CB BLDG 028, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 032

Architectural Estimate

933702

[illegible]

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0323: CB BLDG 032, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:27:46

TITLE PAGE 1

CB BLDG 032, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 032, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/05/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0323: CB BLDG 032, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:27:46

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:27:46

PROJECT CB0323: CB BLDG 032, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0323: CB BLDG 032, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:27:46

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SION	TOTAL COST	UNIT COST
01 Contract	1.00 EA	1,043	0	52	0	1,095	1094.73
CB BLDG 032, ECO #3	1.00 EA	1,043	0	52	0	1,095	1094.73

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0323: CB BLDG 032, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:27:46

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	21	738	5	71	0	814	814.49
CB BLDG 032, ECO #3 OVERHEAD	1.00	EA	21	738	5	71	0	814 41	814.49
SUBTOTAL HOME OFC								855 86	
SUBTOTAL PROFIT								941 81	
SUBTOTAL BOND								1,022 20	
TOTAL INCL INDIRECTS CONTINGENCY								1,043 52	
TOTAL INCL OWNER COSTS								1,095	

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0323: CB BLDG 032, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:27:46

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	814	41	86	81	20	1,043	1042.60

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:27:46

PROJECT CB0323: CB BLDG 032, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

	QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract									
Polyurethane Cmpd, 1/4"x1/4" Joint				4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	3.24	CLF	ARFCA	15	539	3	31	0	573
Mtl Weatherstrip w/Neoprene Bulb				0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	50.00	LF	ACARB	4	131	1	33	0	165
Mtl Weatherstrip for Door Bottom				0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	9.00	LF	ACARB	2	67	1	8	0	76
Bulb									
Contract				21	738	5	71	0	814
CB BLDG 032, ECO #3				21	738	5	71	0	814

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:27:46

PROJECT CB0323: CB BLDG 032, ECO #3 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

*** END OF ERROR REPORT ***

Building 033

Architectural Estimate

933702

[illegible]

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0333: CB BLDG 033, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:35:20

TITLE PAGE 1

CB BLDG 033, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 033, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/05/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0333: CB BLDG 033, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:35:20

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0333: CB BLDG 033, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:35:20

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0333: CB BLDG 033, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:35:20

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00	EA	1,043	0	52	0	1,095	1094.73
CB BLDG 033, ECO #3	1.00	EA	1,043	0	52	0	1,095	1094.73

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0333: CB BLDG 033, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:35:20

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	21	738	5	71	0	814	814.49
CB BLDG 033, ECO #3 OVERHEAD	1.00 EA	21	738	5	71	0	814 41	814.49
SUBTOTAL							855	
HOME OFC							86	
SUBTOTAL							941	
PROFIT							81	
SUBTOTAL							1,022	
BOND							20	
TOTAL INCL INDIRECTS							1,043	
CONTNGENCY							52	
TOTAL INCL OWNER COSTS							1,095	

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0333: CB BLDG 033, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:35:20

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	814	41	86	81	20	1,043	1042.60

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:35:20

PROJECT CB0333: CB BLDG 033, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

	QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract									
Polyurethane Cmpd, 1/4"x1/4" Joint				4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	3.24	CLF	ARFCA	15	539	3	31	0	573
Mtl Weatherstrip w/Neoprene Bulb				0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	50.00	LF	ACARB	4	131	1	33	0	165
Mtl Weatherstrip for Door Bottom				0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	9.00	LF	ACARB	2	67	1	8	0	76
Bulb									
Contract				21	738	5	71	0	814
CB BLDG 033, ECO #3				21	738	5	71	0	814

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:35:20

PROJECT CB0333: CB BLDG 033, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 034

Architectural Estimate

933702

[illegible]

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0343: CB BLDG 034, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:38:39

TITLE PAGE 1

CB BLDG 034, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 034, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/05/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0343: CB BLDG 034, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:38:39

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:38:39

PROJECT CB0343: CB BLDG 034, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0343: CB BLDG 034, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:38:39

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SION	TOTAL COST	UNIT COST
01 Contract	1.00 EA	920	0	46	0	966	965.87
CB BLDG 034, ECO #3	1.00 EA	920	0	46	0	966	965.87

Wed 05 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB0343: CB BLDG 034, ECO #3 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:38:39

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	18	657	5	57	0	719	718.62
CB BLDG 034, ECO #3 OVERHEAD	1.00 EA	18	657	5	57	0	719 36	718.62
SUBTOTAL HOME OFC							755 75	
SUBTOTAL PROFIT							830 72	
SUBTOTAL BOND							902 18	
TOTAL INCL INDIRECTS CONTNGENCY							920 46	
TOTAL INCL OWNER COSTS							966	

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0343: CB BLDG 034, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:38:39

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	719	36	75	72	18	920	919.88

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:38:39

PROJECT CB0343: CB BLDG 034, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract								
Polyurethane Cmpd, 1/4"x1/4"Joint			4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	3.14	CLF ARFCA	15	522	3	30	0	556
Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	34.00	LF ACARB	3	89	1	22	0	112
Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	6.00	LF ACARB	1	45	0	5	0	51
Bulb								
Contract			18	657	5	57	0	719
CB BLDG 034, ECO #3			18	657	5	57	0	719

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 14:38:39

PROJECT CB0343: CB BLDG 034, ECO #3 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 040

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 40		Building Name: TRUSCOTT HALL	
Date Prepared: 5 JAN. 94	Estimator: K. STICK		Sheet 1 of 1
BID ITEM - WALL / ROOF INSULATION			
Description	Quantity	Unit Measurement	
DIV. 07 BLOWN-IN CELLULOSE INSUL. IN 3 1/2"			
STUD WALLS (R=14.0) DRILLING			
& PATCHING DRYWALL & LEAD PAINT			
ABATEMENT INCLUDED	2947	S.F.	
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD.			
R=14.3 (STORAGE RM. WALL INSUL.)	104	S.F.	
DIV. 07 ADHERE 1" RIGID POLYISO. INSUL. BD.			
TO EXIST'G DRYWALL CEIL. R=7.2	4130	S.F.	
(INCLUDE 4005)			
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL	4234	S.F.	
(INCLUDE 4001)			
DIV. 09 INSTALL STD. 2" 'Z' FURR'G @			
24" O.C. BETWEEN 2" RIGID INSUL. BD.	0.56	C.L.F.	
DIV. 09 09920 1221 PAINT'G 1/2" DRYWALL	4234	S.F.	
DIV. 09 INSTALL 4" VINYL COVE BASE	13	L.F.	
DIV. 16 ELEC. WORK ON OUTLETS & SWITCHES	65	EA.	

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB0401: CB BLDG 040, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 14:48:23

TITLE PAGE 1

CB BLDG 040, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 040, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 05/17/94

H C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB0401: CB BLDG 040, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 14:48:23

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB0401: CB BLDG 040, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 14:48:23

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

		AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
01 General Contractor											
OVERHEAD	S		5.00	5.00							
HOME OFC	P		10.00								
PROFIT	S		8.66	5.00							
BOND	P		2.00								
02 Electrical Contractor											
OVERHEAD	P		5.00								
HOME OFC	P		10.00								
PROFIT	C		8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P		2.00								

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB0401: CB BLDG 040, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:48:23

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	18,531	0	927	0	19,458	19457.71
CB BLDG 040, ECO #1	1.00 EA	18,531	0	927	0	19,458	19457.71

Tue 17 May 1994

U.S. Army Corps of Engineers
 PROJECT CB0401: CB BLDG 040, ECO #1 - ESOS Carlisle Barracks
 PREFINAL SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:48:23

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	267	9,181	88	5,208	0	14,476	14476.11
CB BLDG 040, ECO #1 OVERHEAD	1.00 EA	267	9,181	88	5,208	0	14,476 724	14476.11
SUBTOTAL							15,200	
HOME OFC							1,520	
SUBTOTAL							16,720	
PROFIT							1,448	
SUBTOTAL							18,168	
BOND							363	
TOTAL INCL INDIRECTS							18,531	
CONTNGENCY							927	
TOTAL INCL OWNER COSTS							19,458	

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB0401: CB BLDG 040, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:48:23

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	13,621	681	1,430	1,362	342	17,437	17436.56
EL Electrical Contractor	855	43	90	85	21	1,095	1094.60

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 14:48:23

PROJECT CB0401: CB BLDG 040, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

PREFINAL SUBMISSION

DETAIL PAGE 1

01. Contract

	QUANTITY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract									
Blown in Cell. Insul., Includes				0.03	1.11	0.01	0.18	0.00	1.30
Drilling, Patching & Lead Paint	2947.00	SF	ACARA	92	3,271	32	531	0	3,834
Abatement									
2" Polyiso., R14.3 Rigid Insul.				0.01	0.26	0.00	0.90	0.00	1.16
	104.00	SF	ACARA	1	27	0	94	0	121
1" Polyiso., R7.2 Rigid Insul.				0.01	0.24	0.00	0.66	0.00	0.90
	4130.00	SF	ACARA	28	982	9	2,714	0	3,706
1/2" Drywall, One Layer, One Face				0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)	4234.00	SF	ACARB	48	1,699	17	781	0	3,849
For Taping, Spackling, And				34	1,223	13	117		
Std. 2" Z Furrinf, Galv.				2.09	74.50	0.72	28.09	0.00	103.31
	0.56	CLF	ACARA	1	42	0	16	0	58
Interior Roller Work				0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint	4234.00	SF	APTRA	46	1,215	14	808	0	2,036
4" Vinyl Base				0.02	0.61	0.00	0.74	0.00	1.36
	13.00	LF	APAPA	0	8	0	10	0	18
Electrical Work on Outlets &				0.28	11.00	0.04	2.12	0.00	13.16
Switches	65.00	EA	EELEB	18	715	2	138	0	855
Contract				267	9,181	88	5,208	0	14,476
CB BLDG 040, ECO #1				267	9,181	88	5,208	0	14,476

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 14:48:23

PROJECT CB0401: CB BLDG 040, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

*** END OF ERROR REPORT ***

Building 045

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 45	Building Name: BOUQUET HALL	
Date Prepared: 5 JAN. 94	Estimator: DJL	Sheet 1 of 3
BID ITEM WALL / ROOF INSULATION		
Description	Quantity	Unit Measurement
DIV. 06 0611 4201 2x4 WOOD FRAMING AROUND WINDOW OPENINGS	637	B.F.
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD. R=14.3 (WALL INSUL.)	3,826	S.F.
DIV. 07 07210 1017 INSTALL 6" UNFACED FIBERGLASS INSUL. R=19.0 (ROOF INSUL)	5,992	S.F.
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	3,826	S.F.
DIV. 09 INSTALL STD. 2" 'Z' FURRING @ 24" O.C. ON WALLS	24.00	C.L.F.
DIV. 09 09920 1221 PAINTING 1/2" DRYWALL	3,826	S.F.
DIV. 09 INSTALL 4" VINYL BASE	631	L.F.
DIV. 16 ELECTRIC WORK ON OUT. LETS & SWITCHES	60	EA.

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 45

Building Name: BOUQUET HALL

Date Prepared: 5 JAN 94

Estimator: DJL

Sheet 2 of 3

BID ITEM WALL/ROOF INSULATION	
-------------------------------	--

[illegible]

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0451: CB BLDG 045, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:21:59

TITLE PAGE 1

CB BLDG 045, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 045, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/06/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0451: CB BLDG 045, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:21:59

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	S	5.00	5.00							
HOME OFC	P	10.00								
PROFIT	S	8.66	5.00							
BOND	P	2.00								

02 Electrical Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:21:59

PROJECT CB0451: CB BLDG 045, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....1
PROJECT DIRECT SUMMARY - LEVEL 1.....2
CONTRACTOR INDIRECT SUMMARY.....3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0451: CB BLDG 045, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:21:59

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	22,672	0	1,134	0	23,806	23805.71
CB BLDG 045, ECO #1	1.00 EA	22,672	0	1,134	0	23,806	23805.71

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0451: CB BLDG 045, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:21:59

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	290	9,923	100	7,688	0	17,711	17710.91
CB BLDG 045, ECO #1	1.00	EA	290	9,923	100	7,688	0	17,711	17710.91
OVERHEAD								886	
SUBTOTAL								18,596	
HOME OFC								1,860	
SUBTOTAL								20,456	
PROFIT								1,771	
SUBTOTAL								22,228	
BOND								445	
TOTAL INCL INDIRECTS								22,672	
CONTNGENCY								1,134	
TOTAL INCL OWNER COSTS								23,806	

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0451: CB BLDG 045, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:21:59

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	16,850	843	1,769	1,685	423	21,570	21570.20
EL Electrical Contractor	861	43	90	86	22	1,102	1101.91

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:21:59

PROJECT CB0451: CB BLDG 045, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract								
Sills & Plates, 2x4 So Yel Pine			0.02	0.80	0.02	0.24	0.00	1.06
637.00 BF	ACARD		14	510	12	155	0	678
2" Polyiso., R14.3 Rigid Insul.			0.01	0.26	0.00	0.90	0.00	1.16
3826.00 SF	ACARA		28	995	10	3,447	0	4,452
6" Unfaced Batt, R19 Fbgs Insul			0.01	0.30	0.00	0.21	0.00	0.51
5992.00 SF	ACARA		50	1,781	17	1,270	0	3,068
1/2" Drywall, One Layer, One Face			0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)	3826.00 SF	ACARB	43	1,535	16	705	0	3,478
For Taping, Spackling, And			31	1,105	11	106		
Std. 2" Z Furring, Galv.			2.09	74.50	0.72	28.09	0.00	103.31
24.00 CLF	ACARA		50	1,788	17	674	0	2,480
Interior Roller Work			0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint	3826.00 SF	APTRA	41	1,098	12	730	0	1,840
Vinyl Base			0.02	0.61	0.00	0.74	0.00	1.36
631.00 LF	APAPA		14	385	2	468	0	855
Electrical Work on Outlets & Switches			0.28	11.00	0.04	2.12	0.00	13.16
60.00 EA	EELEB		17	660	2	127	0	789
Electrical Work on Wall Mounted Lights			0.93	33.50	0.12	2.12	0.00	35.74
2.00 EA	EELEF		2	67	0	4	0	71
Contract			290	9,923	100	7,688	0	17,711
CB BLDG 045, ECO #1			290	9,923	100	7,688	0	17,711

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:21:59

PROJECT CE0451: CB BLDG 045, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 45

Building Name: BOUQUET HALL

Date Prepared: 5 JAN 94

Estimator: DJL

Sheet 3 of 3

<div style="text-align: right;"> BID ITEM WEATHERSTRIPPING / CAULKING </div>	
---	--

[illegible]

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0453: CB BLDG 045, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:25:15

TITLE PAGE 1

CB BLDG 045, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 045, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/06/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0453: CB BLDG 045, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:25:15

SETTINGS PAGE 1

- CONTRACTOR SETTINGS -

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0453: CB BLDG 045, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:25:15

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3
DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0453: CB BLDG 045, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:25:15

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	1,071	0	54	0	1,124	1124.41
CB BLDG 045, ECO #3	1.00 EA	1,071	0	54	0	1,124	1124.41

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0453: CB BLDG 045, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:25:15

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	20	717	7	113	0	837	836.57
CB BLDG 045, ECO #3	1.00 EA	20	717	7	113	0	837	836.57
OVERHEAD							42	
SUBTOTAL							878	
HOME OFC							88	
SUBTOTAL							966	
PROFIT							84	
SUBTOTAL							1,050	
BOND							21	
TOTAL INCL INDIRECTS							1,071	
CONTINGENCY							54	
TOTAL INCL OWNER COSTS							1,124	

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0453: CB BLDG 045, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:25:15

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	837	42	88	84	21	1,071	1070.86

Thu 06 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB0453: CB BLDG 045, ECO #3 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 01. Contract

TIME 14:25:15

DETAILED ESTIMATE

DETAIL PAGE 1

		QUANTITY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Polyurethane Cmpd, 1/4"x1/4" Joint					4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors		1.20	CLF	ARFCA	6	200	1	11	0	212
Mtl Weatherstrip w/Neoprene Bulb										
For Head and Jamb		120.00	LF	ACARB	0.07	2.62	0.03	0.66	0.00	3.31
					9	315	3	79	0	397
Mtl Weatherstrip for Door Bottom										
Surface Mounted w/Vinyl Bulb		27.00	LF	ACARB	0.21	7.50	0.08	0.85	0.00	8.42
Bulb					6	202	2	23	0	227
Contract					20	717	7	113	0	837
CB BLDG 045, ECO #3					20	717	7	113	0	837

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:25:15

PROJECT CB0453: CB BLDG 045, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 046
Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 46	Building Name: ANNE ELY HALL	
Date Prepared: 5 JAN 94	Estimator: DJL	Sheet 1 of 2
BID ITEM WALL / ROOF INSULATION		
Description	Quantity	Unit Measurement
DIV. 06 0611 4201 2x4 WOOD FRAMING AROUND WINDOW OPENINGS	1410	B.F.
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD. R=14.3 (WALL INSUL.)	9,785	S.F.
DIV. 07 07210 1017 INSTALL 6" UNFACED FIBERGLASS INSUL R=19.0 (ROOF INSUL)	11,031	S.F.
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	9,785	S.F.
DIV. 09 INSTALL STD. 2" "Z" FURRING @ 24" O.C. ON WALLS	61.88	C.L.F.
DIV. 09 09920 1221 PAINTING 1/2" DRYWALL	9,785	S.F.
DIV. 09 INSTALL 4" VINYL BASE	970	L.F.
DIV. 16 ELECTRIC WORK ON OUT- LETS & SWITCHES	60	E.A.

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 46

Building Name: ANNE ELY HALL

Date Prepared: 5 JAN 94

Estimator: DJL

Sheet 2 of 2

BID ITEM	WALL/ROOF INSULATION
----------	----------------------

[illegible]

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0461: CB BLDG 046, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:36:59

TITLE PAGE 1

CB BLDG 046, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 046, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/06/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0461: CB BLDG 046, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:36:59

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	S	5.00	5.00							
HOME OFC	P	10.00								
PROFIT	S	8.66	5.00							
BOND	P	2.00								

02 Electrical Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0461: CB BLDG 046, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:36:59

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0461: CB BLDG 046, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:36:59

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00	EA	52,915	0	2,646	0	55,561	55560.71
CB BLDG 046, ECO #1	1.00	EA	52,915	0	2,646	0	55,561	55560.71

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0461: CB BLDG 046, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:36:59

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	675	23,031	237	18,068	0	41,336	41335.90
CB BLDG 046, ECO #1	1.00 EA	675	23,031	237	18,068	0	41,336	41335.90
OVERHEAD							2,067	
SUBTOTAL							43,403	
HOME OFC							4,340	
SUBTOTAL							47,743	
PROFIT							4,134	
SUBTOTAL							51,877	
BOND							1,038	
TOTAL INCL INDIRECTS							52,915	
CONTNGENCY							2,646	
TOTAL INCL OWNER COSTS							55,561	

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB0461: CB BLDG 046, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:36:59

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	39,842	1,992	4,183	3,985	1,000	51,003	51002.51
EL Electrical Contractor	1,494	75	157	149	37	1,912	1912.46

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:36:59

PROJECT CB0461: CB BLDG 046, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

		QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Sills & Plates, 2x4 So Yel Pine					0.02	0.80	0.02	0.24	0.00	1.06
	1410.00	BF	ACARD		32	1,128	28	344	0	1,500
2" Polyiso., R14.3 Rigid Insul.					0.01	0.26	0.00	0.90	0.00	1.16
	9785.00	SF	ACARA		71	2,544	25	8,816	0	11,385
6" Unfaced Batt, R19 Fbgs Insul					0.01	0.30	0.00	0.21	0.00	0.51
	11031	SF	ACARA		92	3,278	32	2,339	0	5,648
1/2" Drywall, One Layer, One Face					0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)	9785.00	SF	ACARB		110	3,925	40	1,804	0	8,896
For Taping, Spackling, And					79	2,826	29	271		
Std. 2" Z Furring, Galv.					2.09	74.50	0.72	28.09	0.00	103.31
	61.88	CLF	ACARA		129	4,610	45	1,738	0	6,393
Interior Roller Work					0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint	9785.00	SF	APTRA		105	2,807	32	1,867	0	4,706
" Vinyl Base					0.02	0.61	0.00	0.74	0.00	1.36
	970.00	LF	APAPA		22	592	3	720	0	1,314
Electrical Work on Outlets & Switches					0.28	11.00	0.04	2.12	0.00	13.16
	60.00	EA	EELEB		17	660	2	127	0	789
Electrical Work on Wall Mounted Lights					0.93	33.50	0.12	2.12	0.00	35.74
	10.00	EA	EELEF		9	335	1	21	0	357
Electrical Work on Fire Alarm Pull Stations					0.82	32.50	0.11	2.12	0.00	34.73
	5.00	EA	EELEB		4	163	1	11	0	174
Electrical Work on Fire Alarm Bells					0.82	32.50	0.11	2.12	0.00	34.73
	5.00	EA	EELEB		4	163	1	11	0	174
Contract					675	23,031	237	18,068	0	41,336
CB BLDG 046, ECO #1					675	23,031	237	18,068	0	41,336

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:36:59

PROJECT CB0461: CB BLDG 046, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 101
(Typical for 102, 103, 104, 105, 106, 108,
109, 110, 111, 112, 113, and 114)

Architectural Estimate

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 101		Building Name: FORBES AVENUE	
Date Prepared: 4 JAN. 94	Estimator: DJL		Sheet 1 of 3
BID ITEM WALL / ROOF INSULATION			
Description	Quantity	Unit Measurement	
DIV. 02 REMOVAL & RESETTING OF EXIST'G. MILLWORK (BASE & CASINGS).	848	L.F.	
DIV. 06 06111 4201 2x4 WOOD FRAMING AROUND WINDOW & DOOR OPENING'S	391	B.F.	
DIV. 06 1x3 PINE JAMB EXTENSION	434	L.F.	
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD. R=14.3 (WALL INSUL.)	1926	S.F.	
DIV. 07 07210 1017 INSTALL 6" UNFACED FIBERGLASS INSUL. R=19.0 (ROOF INSUL.)	1480	S.F.	
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	1926	S.F.	
DIV. 09 INSTALL STD. 2" 'Z' FURRING @ 24" O.C. ON WALLS	14.79	C.L.F.	
DIV. 09 09920 1221 PAINTING 1/2" DRYWALL	1926	S.F.	

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 101

Building Name: FORBES AVENUE

Date Prepared: 4 JAN 94

Estimator: DJL

Sheet 2 of 3

BID ITEM	WALL/ROOF INSULATION
----------	----------------------

[illegible]

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1011: CB BLDG 101, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:28:01

TITLE PAGE 1

CB BLDG 101, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 101, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/05/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1011: CB BLDG 101, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:28:01

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	S	5.00	5.00							
HOME OFC	P	10.00								
PROFIT	S	8.66	5.00							
BOND	P	2.00								

02 Electrical Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 15:28:01

PROJECT CB1011: CB BLDG 101, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1011: CB BLDG 101, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 15:28:01

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SION	TOTAL COST	UNIT COST
01 Contract	1.00	EA	12,145	0	607	0	12,752	12751.92
CB BLDG 101, ECO #1	1.00	EA	12,145	0	607	0	12,752	12751.92

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1011: CB BLDG 101, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 15:28:01

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	175	5,825	57	3,604	0	9,487	9487.14
CB BLDG 101, ECO #1	1.00	EA	175	5,825	57	3,604	0	9,487	9487.14
OVERHEAD								474	
SUBTOTAL								9,962	
HOME OFC								996	
SUBTOTAL								10,958	
PROFIT								949	
SUBTOTAL								11,907	
BOND								238	
TOTAL INCL INDIRECTS								12,145	
CONTNGENCY								607	
TOTAL INCL OWNER COSTS								12,752	

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1011: CB BLDG 101, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 15:28:01

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	8,961	448	941	896	225	11,471	11471.09
EL Electrical Contractor	526	26	55	53	13	674	673.60

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 15:28:01

PROJECT CB1011: CB BLDG 101, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

		QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Removal & Resetting of Millwork										
	848.00	LF	ULABF		0.03	0.95	0.01	0.00	0.00	0.96
					28	806	6	0	0	812
Sills & Plates, 2x4 So Yel Pine										
Around Doors & Windows										
	391.00	BF	ACARF		0.02	0.80	0.02	0.24	0.00	1.06
					9	313	8	95	0	416
Jamb Extensions										
	434.00	LF	ULABF		0.03	0.79	0.01	0.42	0.00	1.22
					12	343	3	184	0	529
2" Polyiso., R14.3 Rigid Insul.										
	1926.00	SF	ACARA		0.01	0.26	0.00	0.90	0.00	1.16
					14	501	5	1,735	0	2,241
6" Unfaced Batt, R19 Fbgs Insul										
	1480.00	SF	ACARA		0.01	0.30	0.00	0.21	0.00	0.51
					12	440	4	314	0	758
1/2" Drywall, One Layer, One Face										
On Metal Studs or Furring, (13mm)										
For Taping, Spackling, And										
	1926.00	SF	ACARB		0.02	0.69	0.01	0.21	0.00	0.91
					22	773	8	355	0	1,751
					16	556	6	53		
Add. 2" Z Furring, Galv.										
	14.79	CLF	ACARA		2.09	74.50	0.72	28.09	0.00	103.31
					31	1,102	11	415	0	1,528
Interior Roller Work										
One Coat Primer-Two Coats Paint										
	1926.00	SF	APTRA		0.01	0.29	0.00	0.19	0.00	0.48
					21	553	6	367	0	926
Electrical Work on Outlets & Switches										
	40.00	EA	EELEB		0.28	11.00	0.04	2.12	0.00	13.16
					11	440	1	85	0	526
Contract					175	5,825	57	3,604	0	9,487
CB BLDG 101, ECO #1					175	5,825	57	3,604	0	9,487

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 15:28:01

PROJECT CB1011: CB BLDG 101, ECO #1 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 101

Building Name: FORBES AVENUE

Date Prepared: 4 JAN 94

Estimator: DJL

Sheet 3 of 3

	BID ITEM WEATHERSTRIPPING / CAULKING
--	--------------------------------------

[illegible]

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1013: CB BLDG 101, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:33:58

TITLE PAGE 1

CB BLDG 101, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 101, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/05/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1013: CB BLDG 101, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:33:58

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1013: CB BLDG 101, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:33:58

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1013: CB BLDG 101, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 15:33:58

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	2,531	0	127	0	2,658	2657.58
CB BLDG 101, ECO #3	1.00 EA	2,531	0	127	0	2,658	2657.58

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1013: CB BLDG 101, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 15:33:58

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	50	1,777	13	187	0	1,977	1977.27
CB BLDG 101, ECO #3 OVERHEAD	1.00	EA	50	1,777	13	187	0	1,977 99	1977.27
SUBTOTAL HOME OFC								2,076 208	
SUBTOTAL PROFIT								2,284 198	
SUBTOTAL BOND								2,481 50	
TOTAL INCL INDIRECTS CONTINGENCY								2,531 127	
TOTAL INCL OWNER COSTS								2,658	

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1013: CB BLDG 101, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 15:33:58

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	1,977	99	208	198	50	2,531	2531.03

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 15:33:58

PROJECT CB1013: CB BLDG 101, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

Polyurethane Cmpd, 1/4"x1/4" Joint			4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	7.15 CLF	ARFCA	33	1,190	7	68	0	1,265
Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	144.00 LF	ACARB	11	378	4	95	0	476
Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	28.00 LF	ACARB	6	210	2	24	0	236
Bulb								

Contract

			50	1,777	13	187	0	1,977
CB BLDG 101, ECO #3			50	1,777	13	187	0	1,977

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 15:33:58

PROJECT CB1013: CB BLDG 101, ECO #3 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 107

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 107	Building Name: FORBES AVENUE	
Date Prepared: 6 JAN 94	Estimator: DJL	Sheet 1 of 3
BID ITEM WALL/ROOF INSULATION		
Description	Quantity	Unit Measurement
DIV. 02 REMOVAL & RESETTING OF EXIST'G MILLWORK (BASE & CASINGS)	848	L.F.
DIV. 06 0611 4201 2x4 WOOD FRAMING AROUND WINDOW & DOOR OPENINGS	391	B.F.
DIV. 06 1x3 PINE JAMB EXTENSION	434	L.F.
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL BD. R=14.3 (WALL INSUL)	1926	S.F.
DIV. 07 07210 1017 INSTALL 6" UNFACED FIBERGLASS INSUL R=19.0 (ROOF INSUL)	1480	S.F.
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	1926	S.F.
DIV. 09 INSTALL STD. 2" 'Z' FURRING @ 24" O.C. ON WALLS	14.79	C.L.F.
DIV. 09 09920 1221 PAINTING 1/2" DRYWALL	1926	S.F.

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 107

Building Name: **FORBES AVENUE**

Date Prepared:

Estimator:

Sheet 2 of 3

BID ITEM (VALL/ ROOF INSULATION	
---------------------------------	--

[illegible]

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1071: CB BLDG 107, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:48:04

TITLE PAGE 1

CB BLDG 107, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 107, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/06/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1071: CB BLDG 107, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:48:04

SETTINGS PAGE 1

**- CONTRACTOR SETTINGS **-

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	S	5.00	5.00							
HOME OFC	P	10.00								
PROFIT	S	8.66	5.00							
BOND	P	2.00								

02 Electrical Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:48:04

PROJECT CB1071: CB BLDG 107, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1071: CB BLDG 107, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:48:04

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SION	TOTAL COST	UNIT COST
01 Contract	1.00	EA	12,145	0	607	0	12,752	12752.41
CB BLDG 107, ECO #1	1.00	EA	12,145	0	607	0	12,752	12752.41

Thu 06 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB1071: CB BLDG 107, ECO #1 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:48:04

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	175	5,826	57	3,604	0	9,488	9487.61
CB BLDG 107, ECO #1 OVERHEAD	1.00	EA	175	5,826	57	3,604	0	9,488 474	9487.61
SUBTOTAL HOME OFC								9,962 996	
SUBTOTAL PROFIT								10,958 949	
SUBTOTAL BOND								11,907 238	
TOTAL INCL INDIRECTS CONTNGENCY								12,145 607	
TOTAL INCL OWNER COSTS								12,752	

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1071: CB BLDG 107, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:48:04

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	6,720	336	706	672	169	8,603	8603.02
EL Electrical Contractor	2,767	138	291	277	69	3,542	3542.13

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:48:04

PROJECT CB1071: CB BLDG 107, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

		QUANTY	UOM	CREW	ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract											
Removal & Resetting of Millwork											
		848.00	LF	ULABF		0.03	0.95	0.01	0.00	0.00	0.96
						28	806	6	0	0	812
Sills & Plates, 2x4 So Yel Pine											
		391.00	BF	ACARD		0.02	0.80	0.02	0.24	0.00	1.06
						9	313	8	95	0	416
Jamb Extensions											
		434.00	LF	ULABF		0.03	0.79	0.01	0.42	0.00	1.22
						12	343	3	184	0	530
2" Polyiso., R14.3 Rigid Insul.											
		1926.00	SF	ACARA		0.01	0.26	0.00	0.90	0.00	1.16
						14	501	5	1,735	0	2,241
6" Unfaced Batt, R19 Fbgs Insul											
		1480.00	SF	ACARA		0.01	0.30	0.00	0.21	0.00	0.51
						12	440	4	314	0	758
1/2" Drywall, One Layer, One Face											
On Metal Studs or Furring, (13mm)											
For Taping, Spackling, And											
		1926.00	SF	ACARB		0.02	0.69	0.01	0.21	0.00	0.91
						22	773	8	355	0	1,751
						16	556	6	53		
Add. 2" Z Furring, Galv.											
		14.79	CLF	ACARA		2.09	74.50	0.72	28.09	0.00	103.31
						31	1,102	11	415	0	1,528
Interior Roller Work											
One Coat Primer-Two Coats Paint											
		1926.00	SF	APTRA		0.01	0.29	0.00	0.19	0.00	0.48
						21	553	6	367	0	926
Electrical Work on Outlets & Switches											
		40.00	EA	EELEB		0.28	11.00	0.04	2.12	0.00	13.16
						11	440	1	85	0	526
Contract						175	5,826	57	3,604	0	9,488
CB BLDG 107, ECO #1						175	5,826	57	3,604	0	9,488

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:48:04

PROJECT CB1071: CB BLDG 107, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 107

Building Name: FORBES AVENUE

Date Prepared: 6 JAN 94

Estimator: DJL

Sheet 3 of 3

	BID ITEM 1 WEATHERSTRIPPING/CAULKING
--	--------------------------------------

[illegible]

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1073: CB BLDG 107, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:51:13

TITLE PAGE 1

CB BLDG 107, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 107, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/06/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1073: CB BLDG 107, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:51:13

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

*** END TABLE OF CONTENTS ***

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1073: CB BLDG 107, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:51:13

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	2,531	0	127	0	2,658	2657.58
CB BLDG 107, ECO #3	1.00 EA	2,531	0	127	0	2,658	2657.58

Thu 06 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB1073: CB BLDG 107, ECO #3 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:51:13

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	50	1,777	13	187	0	1,977	1977.27
CB BLDG 107, ECO #3 OVERHEAD	1.00 EA	50	1,777	13	187	0	1,977 99	1977.27
SUBTOTAL HOME OFC							2,076 208	
SUBTOTAL PROFIT							2,284 198	
SUBTOTAL BOND							2,481 50	
TOTAL INCL INDIRECTS CONTINGENCY							2,531 127	
TOTAL INCL OWNER COSTS							2,658	

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1073: CB BLDG 107, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:51:13

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	1,977	99	208	198	50	2,531	2531.03

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:51:13

PROJECT CB1073: CB BLDG 107, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

Polyurethane Cmpd, 1/4"x1/4" Joint			4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	7.15 CLF	ARFCA	33	1,190	7	68	0	1,265

Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	144.00 LF	ACARB	11	378	4	95	0	476

Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	28.00 LF	ACARB	6	210	2	24	0	236
Bulb								

Contract			50	1,777	13	187	0	1,977
----------	--	--	----	-------	----	-----	---	-------

CB BLDG 107, ECO #3			50	1,777	13	187	0	1,977
---------------------	--	--	----	-------	----	-----	---	-------

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:51:13

PROJECT CB1073: CB BLDG 107, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

*** END OF ERROR REPORT ***

Building 116

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 116

Building Name: YOUNG HALL

Date Prepared: 6 JAN 94

Estimator: DJL

Sheet 1 of 1

<div style="text-align: right;"> BID ITEM WEATHERSTRIPPING / CAULKING </div>	
---	--

[illegible]

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1163: CB BLDG 116, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:54:37

TITLE PAGE 1

CB BLDG 116, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 116, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/06/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1163: CB BLDG 116, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:54:37
SETTINGS PAGE 1

**- CONTRACTOR SETTINGS **

	AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
--	--------	-----	-------	------	------	------	--------	--------	--------	--------

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:54:37

PROJECT CB1163: CB BLDG 116, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1163: CB BLDG 116, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:54:37

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00	EA	16,467	0	823	0	17,290	17289.83
CB BLDG 116, ECO #3	1.00	EA	16,467	0	823	0	17,290	17289.83

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1163: CB BLDG 116, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:54:37

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	313	11,191	95	1,577	0	12,864	12863.81
CB BLDG 116, ECO #3	1.00 EA	313	11,191	95	1,577	0	12,864	12863.81
OVERHEAD							643	
SUBTOTAL							13,507	
HOME OFC							1,351	
SUBTOTAL							14,858	
PROFIT							1,286	
SUBTOTAL							16,144	
BOND							323	
TOTAL INCL INDIRECTS							16,467	
CONTNGENCY							823	
TOTAL INCL OWNER COSTS							17,290	

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1163: CB BLDG 116, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:54:37

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	12,864	643	1,351	1,286	323	16,467	16466.50

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:54:37

PROJECT CB1163: CB BLDG 116, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

		QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Polyurethane Cmpd, 1/4"x1/4" Joint					4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows					136	4,852	30	278	0	5,160
29.16 CLF ARFCA										
Mtl Weatherstrip w/Neoprene Bulb					0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb					119	4,232	44	1,061	0	5,336
1614.00 LF ACARB										
Mtl Weatherstrip for Door Bottom					0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb					59	2,107	22	238	0	2,367
281.00 LF ACARB										
Bulb										
Contract					313	11,191	95	1,577	0	12,864
CB BLDG 116, ECO #3					313	11,191	95	1,577	0	12,864

Thu 06 Jan 1994

U.S. Army Corps of Engineers

TIME 14:54:37

PROJECT CB1163: CB BLDG 116, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

*** END OF ERROR REPORT ***

Building 118
Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 118	Building Name: THEATER	
Date Prepared: 4 JAN. 94	Estimator: K. STICK	Sheet 1 of 2
BID ITEM - WALL / ROOF INSULATION		
Description	Quantity	Unit Measurement
DIV. 02 DEMO. INTERIOR ACOUSTICAL TILE / WOOD FURR'G STRIPS	2320	S.F.
DIV. 06 06111 4201 2x4 WOOD FRAMING AROUND WINDOW & DOOR OPENINGS	163	B.F.
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD. R = 14.3 (WALL INSUL.)	4973	S.F.
DIV. 07 07210 1017 INSTALL 6" UNFACED FIBERGLASS INSUL. R = 19.0 (ROOF INSUL.)	4508	S.F.
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	4973	S.F.
DIV. 09 INSTALL 2" '2' FURRING @ 24" O.C. BETWEEN 2" RIGID INSUL. BD.	25.55	C.L.F.
DIV. 09 INSTALL 1" THK. SOUND ABSORBING PANELS OVER 2" INSUL. (THEATER)	2000	S.F.

[illegible]

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB1181: CB BLDG 118, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 14:51:44

TITLE PAGE 1

CB BLDG 118, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 118, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 05/17/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB1181: CB BLDG 118, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 14:51:44

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	S	5.00	5.00							
HOME OFC	P	10.00								
PROFIT	S	8.66	5.00							
BOND	P	2.00								

02 Electrical Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 14:51:44

PROJECT CB1181: CB BLDG 118, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB1181: CB BLDG 118, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:51:44

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SIGN	TOTAL COST	UNIT COST
01 Contract	1.00	EA	32,949	0	1,647	0	34,596	34596.47
CB BLDG 118, ECO #1	1.00	EA	32,949	0	1,647	0	34,596	34596.47

Tue 17 May 1994

U.S. Army Corps of Engineers
 PROJECT CB1181: CB BLDG 118, ECO #1 - ESOS Carlisle Barracks
 PREFINAL SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:51:44

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	460	15,265	140	12,201	0	27,605	27604.62
CB BLDG 118, ECO #1	1.00 EA	460	15,265	140	12,201	0	27,605	27604.62
OVERHEAD							954	
SUBTOTAL							28,559	
HOME OFC							2,003	
SUBTOTAL							30,562	
PROFIT							1,908	
SUBTOTAL							32,470	
BOND							479	
TOTAL INCL INDIRECTS							32,949	
CONTNGENCY							1,647	
TOTAL INCL OWNER COSTS							34,596	

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB1181: CB BLDG 118, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:51:44

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
<<< Non-Contracted Work >>>	8,526	0	0	0	0	8,526	8525.81
GC General Contractor	18,684	934	1,962	1,869	469	23,918	23918.07
EL Electrical Contractor	395	20	41	39	10	505	505.14

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 14:51:44

PROJECT CB1181: CB BLDG 118, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

PREFINAL SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY UOM CREW ID			MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract								
Demo. Interior Acoustical Tile & Wood Furring Strips	2320.00	SF ULABF	0.01 15	0.19 441	0.00 3	0.00 0	0.00 0	0.19 444
Sills & Plates, 2x4 So Yel Pine	163.00	BF ACARD	0.02 4	0.80 130	0.02 3	0.24 40	0.00 0	1.06 173
2" Polyiso., R14.3 Rigid Insul.	4973.00	SF ACARA	0.01 36	0.26 1,293	0.00 12	0.90 4,481	0.00 0	1.16 5,786
6" Unfaced Batt, R19 Fbgs Insul	4508.00	SF ACARA	0.01 38	0.30 1,340	0.00 13	0.21 956	0.00 0	0.51 2,308
1/2" Drywall, One Layer, One Face On Metal Studs or Furring, (13mm) For Taping, Spackling, And	4973.00	SF ACARB	0.02 56 40	0.69 1,995 1,436	0.01 21 15	0.21 917 138	0.00 0	0.91 4,521
Std. 2" Z Furring, Galv.	25.55	CLF ACARA	2.09 53	74.50 1,904	0.72 18	28.09 718	0.00 0	103.31 2,640
1" Thick Sound Absorbing Panels	2000.00	SF ACARA	0.03 69	1.23 2,460	0.01 24	1.86 3,710	0.00 0	3.10 6,194
Interior Roller Work One Coat Primer-Two Coats Paint	4973.00	SF APTRA	0.01 53	0.29 1,427	0.00 16	0.19 949	0.00 0	0.48 2,392
4" Vinyl Base	310.00	LF APAPA	0.02 7	0.61 189	0.00 1	0.74 230	0.00 0	1.36 420
Electrical Work on Outlets & Switches	30.00	EA EELEB	0.28 8	11.00 330	0.04 1	2.12 64	0.00 0	13.15 395
Lead Paint Abatement	2320.00	SF ULABB	0.03 80	1.00 2,320	0.01 12	0.00 0	0.00 0	1.01 2,332
Contract			460	15,265	140	12,201	0	27,605
CB BLDG 118, ECO #1			460	15,265	140	12,201	0	27,605

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 14:51:44

PROJECT CB1181: CB BLDG 118, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 122

Architectural Estimate

933702

[illegible]

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1222: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:21:13

TITLE PAGE 1

CB BLDG 122, ECO #2
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 122, Windows
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/10/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1222: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:21:13

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

		AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
01 General Contractor											
OVERHEAD	P	5.00									
HOME OFC	P	10.00									
PROFIT	C	8.65			0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00									

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1222: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:21:13

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1222: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:21:13

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	23,088	0	1,154	0	24,242	24242.45
CB BLDG 122, ECO #2	1.00 EA	23,088	0	1,154	0	24,242	24242.45

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1222: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:21:13

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	369	4,712	49	13,276	0	18,037	18036.63
CB BLDG 122, ECO #2 OVERHEAD	1.00	EA	369	4,712	49	13,276	0	18,037 902	18036.63
SUBTOTAL								18,938	
HOME OFC								1,894	
SUBTOTAL								20,832	
PROFIT								1,803	
SUBTOTAL								22,635	
BOND								453	
TOTAL INCL INDIRECTS								23,088	
CONTNGENCY								1,154	
TOTAL INCL OWNER COSTS								24,242	

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1222: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:21:13

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	18,037	902	1,894	1,803	453	23,088	23088.05

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 14:21:13

PROJECT CB1222: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

3/16" Clear Glass Storm Panel

5964.00 SF AGLAB

0.06	0.79	0.01	2.23	0.00	3.02
369	4,712	49	13,276	0	18,037

Contract

369	4,712	49	13,276	0	18,037
-----	-------	----	--------	---	--------

CB BLDG 122, ECO #2

369	4,712	49	13,276	0	18,037
-----	-------	----	--------	---	--------

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 14:21:13

PROJECT CB1222: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

[illegible]

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1223: CB BLDG 122, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:24:59

TITLE PAGE 1

CB BLDG 122, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 122, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/10/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1223: CB BLDG 122, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:24:59

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 14:24:59

PROJECT CB1223: CB BLDG 122, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

*** END TABLE OF CONTENTS ***

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1223: CB BLDG 122, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:24:59

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SION	TOTAL COST	UNIT COST
01 Contract	1.00	EA	14,922	0	746	0	15,668	15667.82
CB BLDG 122, ECO #3	1.00	EA	14,922	0	746	0	15,668	15667.82

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1223: CB BLDG 122, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:24:59

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	304	10,859	71	727	0	11,657	11657.02
CB BLDG 122, ECO #3	1.00	EA	304	10,859	71	727	0	11,657	11657.02
OVERHEAD								583	
SUBTOTAL								12,240	
HOME OFC								1,224	
SUBTOTAL								13,464	
PROFIT								1,165	
SUBTOTAL								14,629	
BOND								293	
TOTAL INCL INDIRECTS								14,922	
CONTNGENCY								746	
TOTAL INCL OWNER COSTS								15,668	

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1223: CB BLDG 122, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:24:59

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	11,657	583	1,224	1,165	293	14,922	14921.73

Mon 10 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB1223: CB BLDG 122, ECO #3 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 01. Contract

TIME 14:24:59

DETAILED ESTIMATE

DETAIL PAGE 1

		QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Polyurethane Compd, 1/4"x1/4" Joint					4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows					282	10,093	63	579	0	10,735
		60.66	CLF	ARFCA						
Mtl Weatherstrip w/Neoprene Bulb					0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb					13	451	5	113	0	569
		172.00	LF	ACARB						
Mtl Weatherstrip for Door Bottom					0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb					9	315	3	36	0	354
		42.00	LF	ACARB						
Bulb										
Contract					304	10,859	71	727	0	11,657
CB BLDG 122, ECO #3					304	10,859	71	727	0	11,657

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 14:24:59

PROJECT CB1223: CB BLDG 122, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

[illegible]

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1224: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:29:56

TITLE PAGE 1

CB BLDG 122, ECO #2
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 122, Low "E" Glass
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/10/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1224: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:29:56

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 14:29:56

PROJECT CB1224: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

*** END TABLE OF CONTENTS ***

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1224: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:29:56

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SION	TOTAL COST	UNIT COST
01 Contract	1.00 EA	72,628	0	3,631	0	76,259	76258.97
CB BLDG 122, ECO #2	1.00 EA	72,628	0	3,631	0	76,259	76258.97

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1224: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:29:56

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	822	10,505	110	46,123	0	56,737	56737.44
CB BLDG 122, ECO #2 OVERHEAD	1.00 EA	822	10,505	110	46,123	0	56,737 2,837	56737.44
SUBTOTAL							59,574	
HOME OFC							5,957	
SUBTOTAL							65,532	
PROFIT							5,672	
SUBTOTAL							71,204	
BOND							1,424	
TOTAL INCL INDIRECTS							72,628	
CONTNGENCY							3,631	
TOTAL INCL OWNER COSTS							76,259	

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB1224: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:29:56

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	56,737	2,837	5,957	5,672	1,424	72,628	72627.59

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 14:29:56

PROJECT CB1224: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

Solar Film on Ext. Windows

6216.00 SF AGLAB

0.13	1.69	0.02	7.42	0.00	9.13
822	10,505	110	46,123	0	56,737

Contract

822	10,505	110	46,123	0	56,737
-----	--------	-----	--------	---	--------

CB BLDG 122, ECO #2

822	10,505	110	46,123	0	56,737
-----	--------	-----	--------	---	--------

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 14:29:56

PROJECT CB1224: CB BLDG 122, ECO #2 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 201
(Typical for 202, 203, and 204)

Architectural Estimate

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 201		Building Name: MARSHALL RIDGE	
Date Prepared: 5 JAN. 94	Estimator: D.J.L.	Sheet 1 of 3	
BID ITEM WALL / ROOF INSULATION			
Description	Quantity	Unit Measurement	
DIV. 02 REMOVAL & RESETTING OF EXIST'G. MILLWORK (BASE & CASINGS) FIRST FLOOR ONLY	107	L.F.	
DIV. 06 0611 4201 2x4 WOOD FRAMING AROUND WINDOW OPENINGS	32	B.F.	
DIV. 06 1x3 PINE JAMB EXTENSION	48	L.F.	
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD. R=14.3 (WALL INSUL.)	526	S.F.	
DIV. 07 07210 1017 INSTALL 6" UNFACED FIBERGLASS INSUL. R=19.0 (ROOF INSUL.)	876	S.F.	
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	526	S.F.	
DIV. 09 INSTALL STD. 2" 'Z' FURRING @ 24" O.C. ON WALLS	2.00	C.L.F.	
DIV. 09 09920 1221 PAINTING 1/2" DRYWALL	526	S.F.	

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 201

Building Name: MARSHALL RIDGE

Date Prepared: 5 JAN. 94

Estimator: DJL

Sheet 2 of 3

BID ITEM WALL/ROOF INSULATION	
1	1" POLYSTYRENE INSULATION
2	2" POLYSTYRENE INSULATION
3	3" POLYSTYRENE INSULATION
4	4" POLYSTYRENE INSULATION
5	5" POLYSTYRENE INSULATION
6	6" POLYSTYRENE INSULATION
7	7" POLYSTYRENE INSULATION
8	8" POLYSTYRENE INSULATION
9	9" POLYSTYRENE INSULATION
10	10" POLYSTYRENE INSULATION
11	11" POLYSTYRENE INSULATION
12	12" POLYSTYRENE INSULATION
13	13" POLYSTYRENE INSULATION
14	14" POLYSTYRENE INSULATION
15	15" POLYSTYRENE INSULATION
16	16" POLYSTYRENE INSULATION
17	17" POLYSTYRENE INSULATION
18	18" POLYSTYRENE INSULATION
19	19" POLYSTYRENE INSULATION
20	20" POLYSTYRENE INSULATION
21	21" POLYSTYRENE INSULATION
22	22" POLYSTYRENE INSULATION
23	23" POLYSTYRENE INSULATION
24	24" POLYSTYRENE INSULATION
25	25" POLYSTYRENE INSULATION
26	26" POLYSTYRENE INSULATION
27	27" POLYSTYRENE INSULATION
28	28" POLYSTYRENE INSULATION
29	29" POLYSTYRENE INSULATION
30	30" POLYSTYRENE INSULATION
31	31" POLYSTYRENE INSULATION
32	32" POLYSTYRENE INSULATION
33	33" POLYSTYRENE INSULATION
34	34" POLYSTYRENE INSULATION
35	35" POLYSTYRENE INSULATION
36	36" POLYSTYRENE INSULATION
37	37" POLYSTYRENE INSULATION
38	38" POLYSTYRENE INSULATION
39	39" POLYSTYRENE INSULATION
40	40" POLYSTYRENE INSULATION
41	41" POLYSTYRENE INSULATION
42	42" POLYSTYRENE INSULATION
43	43" POLYSTYRENE INSULATION
44	44" POLYSTYRENE INSULATION
45	45" POLYSTYRENE INSULATION
46	46" POLYSTYRENE INSULATION
47	47" POLYSTYRENE INSULATION
48	48" POLYSTYRENE INSULATION
49	49" POLYSTYRENE INSULATION
50	50" POLYSTYRENE INSULATION
51	51" POLYSTYRENE INSULATION
52	52" POLYSTYRENE INSULATION
53	53" POLYSTYRENE INSULATION
54	54" POLYSTYRENE INSULATION
55	55" POLYSTYRENE INSULATION
56	56" POLYSTYRENE INSULATION
57	57" POLYSTYRENE INSULATION
58	58" POLYSTYRENE INSULATION
59	59" POLYSTYRENE INSULATION
60	60" POLYSTYRENE INSULATION
61	61" POLYSTYRENE INSULATION
62	62" POLYSTYRENE INSULATION
63	63" POLYSTYRENE INSULATION
64	64" POLYSTYRENE INSULATION
65	65" POLYSTYRENE INSULATION
66	66" POLYSTYRENE INSULATION
67	67" POLYSTYRENE INSULATION
68	68" POLYSTYRENE INSULATION
69	69" POLYSTYRENE INSULATION
70	70" POLYSTYRENE INSULATION
71	71" POLYSTYRENE INSULATION
72	72" POLYSTYRENE INSULATION
73	73" POLYSTYRENE INSULATION
74	74" POLYSTYRENE INSULATION
75	75" POLYSTYRENE INSULATION
76	76" POLYSTYRENE INSULATION
77	77" POLYSTYRENE INSULATION
78	78" POLYSTYRENE INSULATION
79	79" POLYSTYRENE INSULATION
80	80" POLYSTYRENE INSULATION
81	81" POLYSTYRENE INSULATION
82	82" POLYSTYRENE INSULATION
83	83" POLYSTYRENE INSULATION
84	84" POLYSTYRENE INSULATION
85	85" POLYSTYRENE INSULATION
86	86" POLYSTYRENE INSULATION
87	87" POLYSTYRENE INSULATION
88	88" POLYSTYRENE INSULATION
89	89" POLYSTYRENE INSULATION
90	90" POLYSTYRENE INSULATION
91	91" POLYSTYRENE INSULATION
92	92" POLYSTYRENE INSULATION
93	93" POLYSTYRENE INSULATION
94	94" POLYSTYRENE INSULATION
95	95" POLYSTYRENE INSULATION
96	96" POLYSTYRENE INSULATION
97	97" POLYSTYRENE INSULATION
98	98" POLYSTYRENE INSULATION
99	99" POLYSTYRENE INSULATION
100	100" POLYSTYRENE INSULATION

[illegible]

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2011: CB BLDG 201, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:50:17

TITLE PAGE 1

CB BLDG 201, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 201, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/05/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2011: CB BLDG 201, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:50:17

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	S	5.00	5.00							
HOME OFC	P	10.00								
PROFIT	S	8.66	5.00							
BOND	P	2.00								

02 Electrical Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 15:50:17

PROJECT CB2011: CB BLDG 201, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2011: CB BLDG 201, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 15:50:17

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00	EA	2,909	0	145	0	3,054	3054.22
CB BLDG 201, ECO #1	1.00	EA	2,909	0	145	0	3,054	3054.22

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2011: CB BLDG 201, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 15:50:17

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	38	1,291	13	969	0	2,272	2272.27
CB BLDG 201, ECO #1	1.00 EA	38	1,291	13	969	0	2,272	2272.27
OVERHEAD							114	
SUBTOTAL							2,386	
HOME OFC							239	
SUBTOTAL							2,624	
PROFIT.							227	
SUBTOTAL							2,852	
BOND							57	
TOTAL INCL INDIRECTS							2,909	
CONTINGENCY							145	
TOTAL INCL OWNER COSTS							3,054	

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2011: CB BLDG 201, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 15:50:17

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	2,193	110	230	219	55	2,808	2807.74
EL Electrical Contractor	79	4	8	8	2	101	101.04

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 15:50:17

PROJECT CB2011: CB BLDG 201, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

		QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Removal & Resetting of Millwork										
	107.00	LF	ULABF		0.03	0.95	0.01	0.00	0.00	0.96
					4	102	1	0	0	102
Sills & Plates, 2x4 So Yel Pine										
	32.00	BF	ACARF		0.02	0.80	0.02	0.24	0.00	1.06
					1	26	1	8	0	34
Jamb Extensions										
	48.00	LF	ULABF		0.03	0.79	0.01	0.42	0.00	1.22
					1	38	0	20	0	59
2" Polyiso., R14.3 Rigid Insul.										
	526.00	SF	ACARA		0.01	0.26	0.00	0.90	0.00	1.16
					4	137	1	474	0	612
6" Unfaced Batt, R19 Fbgs Insul										
	876.00	SF	ACARA		0.01	0.30	0.00	0.21	0.00	0.51
					7	260	3	186	0	449
1/2" Drywall, One Layer, One Face										
On Metal Studs or Furring, (13mm)	526.00	SF	ACARB		0.02	0.69	0.01	0.21	0.00	0.91
For Taping, Spackling, And					6	211	2	97	0	478
					4	152	2	15		
Add. 2" Z Furring, Galv.										
	2.00	CLF	ACARA		2.09	74.50	0.72	28.09	0.00	103.31
					4	149	1	56	0	207
Interior Roller Work										
One Coat Primer-Two Coats Paint	526.00	SF	APTRA		0.01	0.29	0.00	0.19	0.00	0.48
					6	151	2	100	0	253
Electrical Work on Outlets & Switches										
	6.00	EA	EELEB		0.28	11.00	0.04	2.12	0.00	13.16
					2	66	0	13	0	79
Contract					38	1,291	13	969	0	2,272
CB BLDG 201, ECO #1					38	1,291	13	969	0	2,272

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 15:50:17

PROJECT CB2011: CB BLDG 201, ECO #1 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 201

Building Name: MARSHALL RIDGE

Date Prepared: 5 JAN. 94

Estimator: DJL

Sheet 3 of 3

BID ITEM	WEATHERSTRIPPING / CAULKING
----------	-----------------------------

[illegible]

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2013: CB BLDG 201, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:53:41

TITLE PAGE 1

CB BLDG 201, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 201, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/05/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2013: CB BLDG 201, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:53:41

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2013: CB BLDG 201, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:53:41

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3
DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2013: CB BLDG 201, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 15:53:41

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00	EA	1,367	0	68	0	1,436	1435.81
CB BLDG 201, ECO #3	1.00	EA	1,367	0	68	0	1,436	1435.81

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2013: CB BLDG 201, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 15:53:41

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	27	973	7	89	0	1,068	1068.26
CB BLDG 201, ECO #3 OVERHEAD	1.00 EA	27	973	7	89	0	1,068 53	1068.26
SUBTOTAL							1,122	
HOME OFC							112	
SUBTOTAL							1,234	
PROFIT.							107	
SUBTOTAL							1,341	
BOND							27	
TOTAL INCL INDIRECTS							1,367	
CONTNGENCY							68	
TOTAL INCL OWNER COSTS							1,436	

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2013: CB BLDG 201, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 15:53:41

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	1,068	53	112	107	27	1,367	1367.44

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 15:53:41

PROJECT CB2013: CB BLDG 201, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract								
Polyurethane Cmpd, 1/4"x1/4"Joint			4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	4.63	CLF ARFCA	22	770	5	44	0	819
Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	60.00	LF ACARB	4	157	2	39	0	198
Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	6.00	LF ACARB	1	45	0	5	0	51
Bulb								
Contract			27	973	7	89	0	1,068
CB BLDG 201, ECO #3			27	973	7	89	0	1,068

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 15:53:41

PROJECT CB2013: CB BLDG 201, ECO #3 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 205
(Typical for 206, 207, 208, 209, 210, 211,
212, 213, 214, 215, 216, 217,
218, 219, and 220)

Architectural Estimate

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. **205**

Building Name: **MARSHALL RIDGE**

Date Prepared: **5 JAN 94**

Estimator: **DJL**

Sheet **1** of **3**

BID ITEM WALL / ROOF INSULATION

Description	Quantity	Unit Measurement
DIV. 02 REMOVAL & RESETTNG OF EXISTG. MILLWORK (BASE & CASING) FIRST FLOOR ONLY	214	L.F.
DIV. 06 0611 4201 2x4 WOOD FRAMING AROUND WINDOW OPENINGS	64	B.F.
DIV. 06 1x3 PINE JAMB EXTENSION	96	L.F.
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD. R=14.3 (WALL INSUL.)	1052	S.F.
DIV. 07 07210 1017 INSTALL 6" UNFACED FIBERGLASS INSUL. R=19.0 (ROOF INSUL.)	1752	S.F.
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	1052	S.F.
DIV. 09 INSTALL STD. 2" 'Z' FURRING @ 24" O.C. ON WALLS	4.00	C.L.F.
DIV. 09 09920 1221 PAINTING 1/2" DRYWALL	1052	S.F.

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 205

Building Name: MARSHALL RIDGE

Date Prepared: 5 JAN 94

Estimator: DJL

Sheet 2 of 3

BID ITEM WALL/ROOF INSULATION	
-------------------------------	--

[illegible]

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2051: CB BLDG 205, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:07:41

TITLE PAGE 1

CB BLDG 205, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 205, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/05/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2051: CB BLDG 205, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:07:41

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	S	5.00	5.00							
HOME OFC	P	10.00								
PROFIT	S	8.66	5.00							
BOND	P	2.00								

02 Electrical Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 16:07:41

PROJECT CB2051: CB BLDG 205, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

*** END TABLE OF CONTENTS ***

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2051: CB BLDG 205, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 16:07:41

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	5,818	0	291	0	6,108	6108.44
CB BLDG 205, ECO #1	1.00 EA	5,818	0	291	0	6,108	6108.44

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2051: CB BLDG 205, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 16:07:41

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	77	2,582	25	1,937	0	4,545	4544.54
CB BLDG 205, ECO #1 OVERHEAD	1.00	EA	77	2,582	25	1,937	0	4,545 227	4544.54
SUBTOTAL HOME OFC								4,772 477	
SUBTOTAL PROFIT								5,249 455	
SUBTOTAL BOND								5,703 114	
TOTAL INCL INDIRECTS CONTNGENCY								5,818 291	
TOTAL INCL OWNER COSTS								6,108	

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2051: CB BLDG 205, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 16:07:41

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	4,387	219	461	439	110	5,615	5615.49
EL Electrical Contractor	158	8	17	16	4	202	202.08

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 16:07:41

PROJECT CB2051: CB BLDG 205, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

		QUANTITY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Removal & Resetting of Millwork					0.03	0.95	0.01	0.00	0.00	0.96
	214.00	LF	ULABF		7	203	2	0	0	205
Sills & Plates, 2x4 So Yel Pine					0.02	0.80	0.02	0.24	0.00	1.06
	64.00	BF	ACARF		1	51	1	16	0	68
Jamb Extensions					0.03	0.79	0.01	0.42	0.00	1.22
	96.00	LF	ULABF		3	76	1	41	0	117
6" Unfaced Batt, R19 Fbgs Insul					0.01	0.30	0.00	0.21	0.00	0.51
	1752.00	SF	ACARA		15	521	5	371	0	897
2' Polyiso., R14.3 Rigid Insul.					0.01	0.26	0.00	0.90	0.00	1.16
	1052.00	SF	ACARA		8	274	3	948	0	1,224
1/2" Drywall, One Layer, One Face					0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)	1052.00	SF	ACARB		12	422	4	194	0	956
For Taping, Spackling, And					9	304	3	29		
Add. 2" Z Furring, Galv.					2.09	74.50	0.72	28.09	0.00	103.31
	4.00	CLF	ACARA		8	298	3	112	0	413
Interior Roller Work					0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint	1052.00	SF	APTRA		11	302	3	201	0	506
Electrical Work on Outlets & Switches					0.28	11.00	0.04	2.12	0.00	13.16
	12.00	EA	EELEB		3	132	0	25	0	158
Contract					77	2,582	25	1,937	0	4,545
CB BLDG 205, ECO #1					77	2,582	25	1,937	0	4,545

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 16:07:41

PROJECT CB2051: CB BLDG 205, ECO #1 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 205

Building Name:	MARSHALL RIDGE
----------------	----------------

Date Prepared: 5 JAN. 94

Estimator: DJL

Sheet 3 of 3

BID ITEM	WEATHERSTRIPPING/CAULKING
----------	---------------------------

[illegible]

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2053: CB BLDG 205, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:11:52

TITLE PAGE 1

CB BLDG 205, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 205, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/05/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

** CONTRACTOR SETTINGS **

		AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
--	--	--------	-----	-------	------	------	------	--------	--------	--------	--------

01 General Contractor

OVERHEAD	P	5.00									
HOME OFC	P	10.00									
PROFIT	C	8.65			0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00									

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 16:11:52

PROJECT CB2053: CB BLDG 205, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2053: CB BLDG 205, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 16:11:52

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SION	TOTAL COST	UNIT COST
01 Contract	1.00 EA	2,735	0	137	0	2,872	2871.62
CB BLDG 205, ECO #3	1.00 EA	2,735	0	137	0	2,872	2871.62

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2053: CB BLDG 205, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 16:11:52

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	54	1,945	14	177	0	2,137	2136.51
CB BLDG 205, ECO #3	1.00 EA	54	1,945	14	177	0	2,137	2136.51
OVERHEAD							107	
SUBTOTAL							2,243	
HOME OFC							224	
SUBTOTAL							2,468	
PROFIT							214	
SUBTOTAL							2,681	
BOND							54	
TOTAL INCL INDIRECTS							2,735	
CONTNGENCY							137	
TOTAL INCL OWNER COSTS							2,872	

Wed 05 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2053: CB BLDG 205, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 16:11:52

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	2,137	107	224	214	54	2,735	2734.87

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 16:11:52

PROJECT CB2053: CB BLDG 205, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

Polyurethane Cmpd, 1/4"x1/4" Joint			4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	9.26	CLF ARFCA	43	1,541	10	88	0	1,639

Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	120.00	LF ACARB	9	315	3	79	0	397

Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	12.00	LF ACARB	3	90	1	10	0	101
Bulb								

Contract			54	1,945	14	177	0	2,137
----------	--	--	----	-------	----	-----	---	-------

CB BLDG 205, ECO #3			54	1,945	14	177	0	2,137
---------------------	--	--	----	-------	----	-----	---	-------

Wed 05 Jan 1994

U.S. Army Corps of Engineers

TIME 16:11:52

PROJECT CB2053: CB BLDG 205, ECO #3 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

*** END OF ERROR REPORT ***

Building 253
Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 253		Building Name: MEDICAL SUPPLY	
Date Prepared: 3 JAN. 94	Estimator: DJL		Sheet 1 of 2
BID ITEM WALL/ROOF INSULATION			
Description	Quantity	Unit Measurement	
DIV. 06 0611 4201 2x4 WOOD FRAMING @ WINDOW & DOOR OPENINGS	375	B.F.	
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL BD. R=14.3 WALL INSULATION	2,237	S.F.	
DIV. 07 07210 1017 INSTALL 6" UNFACED FIBERGLASS INSUL. R=19.0 (ROOF INSUL)	4,500	S.F.	
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	2,237	S.F.	
DIV. 09 INSTALL STD. 2" 'Z' FURRING @ 24" O.C. ON WALLS	16.26	C.L.F.	
DIV. 09 INSTALL 4" VINYL BASE	210	L.F.	
DIV. 09 09920 1221 PAINTING 1/2" DRYWALL	2,237	S.F.	
DIV. 16 ELECT. WORK ON OUTLETS & SWITCHES	15	EA.	

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 253

Building Name: MEDICAL SUPPLY

Date Prepared: 3 JAN. 94

Estimator: D.N.L

Sheet 2 of 2

BID ITEM	
----------	--

[illegible]

Mon 03 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2531: CB BLDG 253, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:23:50

TITLE PAGE 1

CB BLDG 253, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 253, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/03/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:23:50

PROJECT CB2531: CB BLDG 253, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
--------	-----	-------	------	------	------	--------	--------	--------	--------

01 General Contractor

OVERHEAD	S	5.00	5.00
HOME OFC	P	10.00	
PROFIT	S	8.66	5.00
BOND	P	2.00	

02 Electrical Contractor

OVERHEAD	P	5.00							
HOME OFC	P	10.00							
PROFIT	C	8.66	0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00							

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:23:50

PROJECT CB2531: CB BLDG 253, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

CONTENTS PAGE 1

OF CONTENTS

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....1
PROJECT DIRECT SUMMARY - LEVEL 1.....2
CONTRACTOR INDIRECT SUMMARY.....3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:23:50

PROJECT CB2531: CB BLDG 253, ECO #1 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 1

** PROJECT OWNER SUMMARY - LEVEL 1 **

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SION	TOTAL COST	UNIT COST
01 Contract	1.00 EA	13,825	0	691	0	14,516	14515.97
CB BLDG 253, ECO #1	1.00 EA	13,825	0	691	0	14,516	14515.97

LABOR ID: R01 92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2531: CB BLDG 253, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 15:23:50

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	178	6,124	63	4,613	0	10,800	10799.55

CB BLDG 253, ECO #1 OVERHEAD	1.00 EA	178	6,124	63	4,613	0	10,800 540	10799.55
SUBTOTAL HOME OFC							----- 11,340 1,134	
SUBTOTAL PROFIT							----- 12,473 1,080	
SUBTOTAL BOND							----- 13,554 271	
TOTAL INCL INDIRECTS CONTINGENCY							----- 13,825 691	
TOTAL INCL OWNER COSTS							----- 14,516	

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:23:50

PROJECT CB2531: CB BLDG 253, ECO #1 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 3

** CONTRACTOR INDIRECT SUMMARY **

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	10,390	520	1,091	1,039	261	13,301	13300.67
EL Electrical Contractor	409	20	43	41	10	524	524.07

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:23:50

PROJECT CB2531: CB BLDG 253, ECO #1 - ESOS Carlisle Barracks

LED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY UOM CREW ID			MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract								
Sills & Plates, 2x4 So Yel Pine			0.02	0.80	0.02	0.24	0.00	1.06
375.00 BF ACARD			8	300	7	91	0	399
2" Polyiso., R14.3, Rigid Insul.			0.01	0.26	0.00	0.90	0.00	1.17
2237.00 SF ACARA			17	592	6	2,016	0	2,613
6" Unfaced Batt, R19 Fbgs Insul			0.01	0.30	0.00	0.21	0.00	0.51
4500.00 SF ACARA			38	1,337	13	954	0	2,304
1/2" Drywall, One Layer, One Face			0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)	2237.00 SF	ACARB	25	897	9	412	0	2,034
For Taping, Spackling, And			18	646	7	62		
Std. 2' Z Furring, Galv.			2.09	74.50	0.72	28.09	0.00	103.31
16.26 CLF ACARA			34	1,211	12	457	0	1,680
1/2" Vinyl Base			0.02	0.61	0.00	0.74	0.00	1.36
210.00 LF APAPA			5	128	1	156	0	285
Interior Roller Work			0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint	2237.00 SF	APTRA	24	642	7	427	0	1,076
Electrical Work on Outlets & Switches	15.00 EA	EELEB	0.28	11.00	0.04	2.12	0.00	13.16
			4	165	1	32	0	197
Electrical Work on Wall Mtd. Security Lights	3.00 EA	EELEB	1.73	68.35	0.22	2.12	0.00	70.69
			5	205	1	6	0	212
Contract			178	6,124	63	4,613	0	10,800
CB BLDG 253, ECO #1			178	6,124	63	4,613	0	10,800

LABOR ID: R01_92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UPB ID: NAT92A

Mon 03 Jan 1994

U.S. Army Corps of Engineers

TIME 15:23:50

PROJECT CB2531: CB BLDG 253, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 259

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 259		Building Name: WILSON HOUSE	
Date Prepared: 10 JAN. 94	Estimator: K. STICK	Sheet 1 of 3	
BID ITEM - WALL / ROOF INSULATION			
Description	Quantity	Unit Measurement	
DIV. 02 REMOVAL & RESETTING OF			
EXIST. MILLWORK (BASE & CASING)	786	L.F.	
DIV. 06 06111 4201 2x4 WOOD FRAMING			
AROUND WINDOW & DOOR OPENINGS	374	B.F.	
DIV. 06 1x3 PINE JAMB EXTENSIONS	562	L.F.	
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD.			
R=14.3 (WALL INSUL.)	1699	S.F.	
DIV. 07 07210 1017 INSTALL 6" UNFACED			
FIBERGLASS INSUL. R=19.0			
(ROOF INSULATION)	1340	S.F.	
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL			
(INCLUDE 4001)	1699	S.F.	
DIV. 09 INSTALL STD. 2" '2' FURRING @			
24" O.C. BETWEEN 2" RIGID INSUL. BD.	12.32	C.L.F.	

[illegible]

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2591: CB BLDG 259, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:00:07

TITLE PAGE 1

CB BLDG 259, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 259, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/10/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2591: CB BLDG 259, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:00:07

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

		AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
01 General Contractor											
OVERHEAD	S		5.00	5.00							
HOME OFC	P		10.00								
PROFIT	S		8.66	5.00							
BOND	P		2.00								
02 Electrical Contractor											
OVERHEAD	P		5.00								
HOME OFC	P		10.00								
PROFIT	C		8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P		2.00								

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2591: CB BLDG 259, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:00:07

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2591: CB BLDG 259, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 15:00:07

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SION	TOTAL COST	UNIT COST
01 Contract	1.00	EA	12,056	0	603	0	12,659	12658.99
CB BLDG 259, ECO #1	1.00	EA	12,056	0	603	0	12,659	12658.99

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2591: CB BLDG 259, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 15:00:07

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	186	6,041	60	3,318	0	9,418	9418.01
CB BLDG 259, ECO #1	1.00	EA	186	6,041	60	3,318	0	9,418	9418.01
OVERHEAD								471	
SUBTOTAL								9,889	
HOME OFC								989	
SUBTOTAL								10,878	
PROFIT								942	
SUBTOTAL								11,820	
BOND								236	
TOTAL INCL INDIRECTS								12,056	
CONTINGENCY								603	
TOTAL INCL OWNER COSTS								12,659	

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2591: CB BLDG 259, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 15:00:07

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	8,826	441	927	883	222	11,298	11298.39
EL Electrical Contractor	592	30	62	59	15	758	757.80

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 15:00:07

PROJECT CB2591: CB BLDG 259, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

		QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Removal & Resetting of Millwork					0.03	0.95	0.01	0.00	0.00	0.96
	786.00	LF	ULABF		26	747	6	0	0	752
Sills & Plates, 2x4 So Yel Pine					0.02	0.80	0.02	0.24	0.00	1.06
	374.00	BF	ACARD		8	299	7	91	0	398
Jamb Extensions					0.03	0.79	0.01	0.42	0.00	1.22
	562.00	LF	ULABF		15	444	3	238	0	686
2" Polyiso, R14.3 Rigid Insul.					0.01	0.26	0.00	0.90	0.00	1.16
	1699.00	SF	ACARA		12	442	4	1,531	0	1,977
6" Unfaced Batt, R19 Fbgs Insul					0.01	0.30	0.00	0.21	0.00	0.51
	1340.00	SF	ACARA		11	398	4	284	0	686
1/2" Drywall, One Layer, One Face					0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)	1699.00	SF	ACARB		19	682	7	313	0	1,545
For Taping, Spackling, And					14	491	5	47		
Std 2" Z Furring, Galv.					2.09	74.50	0.72	28.09	0.00	103.31
	12.32	CLF	ACARA		26	918	9	346	0	1,273
Interior Roller Work					0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint	1699.00	SF	APTRA		18	487	5	324	0	817
Paint, Int Wd Trim, 1 Prime, 2 Paint					0.04	1.14	0.01	0.08	0.00	1.23
Enamel Primer, Alkyd or Latex Pnt	562.00	LF	APTRA		24	638	7	48	0	693
Electrical Work on Outlets & Switches					0.28	11.00	0.04	2.12	0.00	13.16
	45.00	EA	EELEB		13	495	2	95	0	592
Contract					186	6,041	60	3,318	0	9,418
CB BLDG 259, ECO #1					186	6,041	60	3,318	0	9,418

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 15:00:07

PROJECT CB2591: CB BLDG 259, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

[illegible]

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2593: CB BLDG 259, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:04:36

TITLE PAGE 1

CB BLDG 259, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 259, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/10/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2593: CB BLDG 259, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:04:36

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

		AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
01 General Contractor											
OVERHEAD	P	5.00									
HOME OFC	P	10.00									
PROFIT	C	8.65			0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00									

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2593: CB BLDG 259, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:04:36

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2593: CB BLDG 259, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 15:04:36

SUMMARY PAGE 1

		QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01	Contract	1.00 EA	1,793	0	90	0	1,883	1882.83
	CB BLDG 259, ECO #3	1.00 EA	1,793	0	90	0	1,883	1882.83

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2593: CB BLDG 259, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 15:04:36

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	36	1,281	9	110	0	1,401	1400.85
CB BLDG 259, ECO #3 OVERHEAD	1.00 EA	36	1,281	9	110	0	1,401 70	1400.85
SUBTOTAL							1,471	
HOME OFC							147	
SUBTOTAL							1,618	
PROFIT							140	
SUBTOTAL							1,758	
BOND							35	
TOTAL INCL INDIRECTS							1,793	
CONTINGENCY							90	
TOTAL INCL OWNER COSTS							1,883	

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB2593: CB BLDG 259, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 15:04:36

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	1,401	70	147	140	35	1,793	1793.17

Mon 10 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB2593: CB BLDG 259, ECO #3 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 01. Contract

TIME 15:04:36

DETAILED ESTIMATE

DETAIL PAGE 1

		QUANTY	UOM	CREW	ID	MANERS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract											
Polyurethane Cmpd, 1/4"x1/4" Joint						4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows						26	935	6	54	0	995
5.62 CLF ARFCA											
Mtl Weatherstrip w/Neoprene Bulb						0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb						4	128	1	32	0	162
49.00 LF ACARB											
Mtl Weatherstrip for Door Bottom						0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb						6	217	2	25	0	244
29.00 LF ACARB											
Bulb											
Contract						36	1,281	9	110	0	1,401
CB BLDG 259, ECO #3						36	1,281	9	110	0	1,401

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 15:04:36

PROJECT CB2593: CB BLDG 259, ECO #3 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

*Building 311
(Typical for 312)*

Architectural Estimate

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 311		Building Name: BUILDING 311	
Date Prepared: 6 JAN 94		Estimator: DJL	Sheet 1 of 2
BID ITEM WALL/ROOF INSULATION			
Description	Quantity	Unit Measurement	
DIV. 02 REMOVAL & RESETTNG OF EXIST'G. MILLWORK (BASE & CASINGS)	1072	L.F.	
DIV. 02 REMOVAL OF HORSEHAIR PLASTER & WOOD LATH.	3868	S.F.	
DIV. 07 07210 1003 INSTALL 4" KRAFT FACED FIBERGLASS INSUL R= 11.0 WALL INSULATION	3868	S.F.	
DIV. 07 07210 1017 INSTALL 6" UNFACED FIBERGLASS INSUL. R= 19.0 (CLG. INSUL)	2060	S.F.	
DIV. 09 09260 1002 INSTALL 1/2" DRY- WALL (INCLUDE 4001)	3868	S.F.	
DIV. 09 09220 1221 PAINTING 1/2" DRYWALL	3868	S.F.	
DIV. 16 ELECT. WORK ON OUTLETS & SWITCHES	46	EA.	
DIV. 2 LEAD PAINT ABATEMENT	3868	S.F.	

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3111: CB BLDG 311, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 15:50:30

TITLE PAGE 1

CB BLDG 311, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 023, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 05/17/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3111: CB BLDG 311, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 15:50:30

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	S	5.00	5.00							
HOME OFC	P	10.00								
PROFIT	S	8.66	5.00							
BOND	P	2.00								

02 Electrical Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3111: CB BLDG 311, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 15:50:30

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....1
PROJECT DIRECT SUMMARY - LEVEL 1.....2
CONTRACTOR INDIRECT SUMMARY.....3

DETAILED ESTIMATE DETAIL PAGE

01. Contract.....1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3111: CB BLDG 311, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 15:50:30

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	18,325	0	916	0	19,242	19241.55
CB BLDG 311, ECO #1	1.00 EA	18,325	0	916	0	19,242	19241.55

Tue 17 May 1994

U.S. Army Corps of Engineers
 PROJECT CB3111: CB BLDG 311, ECO #1 - ESOS Carlisle Barracks
 PREFINAL SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 15:50:30

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	398	12,402	97	2,666	0	15,166	15166.08
CB BLDG 311, ECO #1 OVERHEAD	1.00 EA	398	12,402	97	2,666	0	15,166 564	15166.08
SUBTOTAL HOME OFC							15,730 1,184	
SUBTOTAL PROFIT							16,914 1,128	
SUBTOTAL BOND							18,042 283	
TOTAL INCL INDIRECTS CONTINGENCY							18,325 916	
TOTAL INCL OWNER COSTS							19,242	

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3111: CB BLDG 311, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 15:50:30

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
<<< Non-Contracted Work >>>	3,888	0	0	0	0	3,888	3888.06
GC General Contractor	10,673	534	1,121	1,068	268	13,663	13662.58
EL Electrical Contractor	605	30	64	60	15	775	774.65

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 15:50:30

PROJECT CB3111: CB BLDG 311, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

PREFINAL SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY UOM CREW ID			MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract								
Removal & Resetting of Millwork			0.03	0.95	0.01	0.00	0.00	0.96
1072.00 LF	ULABF		35	1,018	8	0	0	1,026
Removal of Horsehair Plaster & Wood Lathe			0.01	0.38	0.00	0.00	0.00	0.38
3868.00 SF	ULABF		51	1,470	11	0	0	1,481
4" Kraft Faced, R11 Fbgs Insul			0.01	0.30	0.00	0.14	0.00	0.44
3868.00 SF	ACARA		32	1,149	11	533	0	1,694
6" Unfaced Batt, R19 Fbgs Insul			0.01	0.30	0.00	0.21	0.00	0.51
2060.00 SF	ACARA		17	612	6	437	0	1,055
1/2" Drywall, One Layer, One Face On Metal Studs or Furring, (13mm)			0.02	0.69	0.01	0.22	0.00	0.92
3868.00 SF	ACARB		44	1,552	16	749	0	3,557
For Taping, Spackling, And			31	1,117	11	112		
Interior Roller Work			0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint			42	1,110	12	738	0	1,860
3868.00 SF	APTRA							
Electrical Work on Switches & Outlets			0.28	11.00	0.04	2.12	0.00	13.16
46.00 EA	EELEB		13	506	2	98	0	605
Lead Paint Abatement			0.03	1.00	0.01	0.00	0.00	1.01
3868.00 SF	ULABB		134	3,868	20	0	0	3,888
Contract			398	12,402	97	2,666	0	15,166
CB BLDG 311, ECO #1			398	12,402	97	2,666	0	15,166

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 15:50:30

PROJECT CB3111: CB BLDG 311, ECO #1 - ESOS Carlisle Barracks

ERROR REPORT

PREFINAL SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 311

Building Name:	BUILDING 311
----------------	--------------

Date Prepared: 6 JAN 94

Estimator: DJL

Sheet 2 of 2

	BID ITEM WEATHERSTRIPPING / CAULKING
--	--------------------------------------

[illegible]

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3113: CB BLDG 311, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:46:17

TITLE PAGE 1

CB BLDG 311, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 311, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/06/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3113: CB BLDG 311, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:46:17

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3113: CB BLDG 311, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:46:17

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3113: CB BLDG 311, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 15:46:17

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00	EA	2,327	0	116	0	2,444	2443.64
CB BLDG 311, ECO #3	1.00	EA	2,327	0	116	0	2,444	2443.64

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3113: CB BLDG 311, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 15:46:17

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	46	1,631	12	174	0	1,818	1818.09
CB BLDG 311, ECO #3 OVERHEAD	1.00 EA	46	1,631	12	174	0	1,818 91	1818.09
SUBTOTAL HOME OFC							1,909 191	
SUBTOTAL PROFIT							2,100 182	
SUBTOTAL BOND							2,282 46	
TOTAL INCL INDIRECTS CONTINGENCY							2,327 116	
TOTAL INCL OWNER COSTS							2,444	

Thu 06 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3113: CB BLDG 311, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 15:46:17

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	1,818	91	191	182	46	2,327	2327.28

Thu 06 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB3113: CB BLDG 311, ECO #3 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 01. Contract

TIME 15:46:17

DETAILED ESTIMATE

DETAIL PAGE 1

		QUANTITY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Polyurethane Cmpd, 1/4"x1/4" Joint					4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows					30	1,065	7	61	0	1,133
		6.40	CLF	ARFCA						
Mtl Weatherstrip w/Neoprene Bulb					0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb					10	357	4	89	0	450
		136.00	LF	ACARB						
Mtl Weatherstrip for Door Bottom					0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb					6	210	2	24	0	236
		28.00	LF	ACARB						
Bulb										
Contract					46	1,631	12	174	0	1,818
CB BLDG 311, ECO #3					46	1,631	12	174	0	1,818

Fri 06 Jan 1994

U.S. Army Corps of Engineers

TIME 15:46:17

PROJECT CB3113: CB BLDG 311, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 313

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 313 Building Name: OFFICERS CLUB

Date Prepared: 11 JAN 94 Estimator: DJL Sheet 1 of 3

BID ITEM WALL/ ROOF INSULATION

Description	Quantity	Unit Measurement
DIV.02 REMOVAL & RESETTNG OF EXIST'G. MILLWORK (BASE & CASINGS)	815	L.F.
DIV.06 0611 4201 2x4 WOOD FRAMING AROUND WINDOW & DOOR OPENINGS	355	B.F.
DIV.06 1x3 PINE JAMB EXTENSION	533	L.F.
DIV.07 INSTALL 2" RIGID POLYISO. INSUL. BD. R= 14.3 (WALL INSUL.)	2636	S.F.
DIV.07 07210 1003 INSTALL 4" KRAFT FACED FIBERGLASS INSUL. R=11.0 (WALL INSULATION)	2584	S.F.
DIV.09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	2636	S.F.
DIV.09 INSTALL STD. 2" 'Z' FURRING @ 24" O.C. ON WALLS	17.28	C.L.F.
DIV.09 09220 1221 PAINTING 1/2" DRYWALL	2636	S.F.

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 313

Building Name: OFFICERS CLUB

Date Prepared: 11 JAN. 94

Estimator: DJL

Sheet 2 of 3

BID ITEM WALL/ROOF INSULATION	
-------------------------------	--

[illegible]

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3131: CB BLDG 313, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:23:35

TITLE PAGE 1

CB BLDG 313, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 313, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/13/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 14:23:35

PROJECT CB3131: CB BLDG 313, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
--------	-----	-------	------	------	------	--------	--------	--------	--------

01 General Contractor

OVERHEAD	S	5.00	5.00
HOME OFC	P	10.00	
PROFIT	S	8.66	5.00
BOND	P	2.00	

02 Electrical Contractor

OVERHEAD	P	5.00							
HOME OFC	P	10.00							
PROFIT	C	8.66	0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00							

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 14:23:35

PROJECT CB3131: CB BLDG 313, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 14:23:35

PROJECT CB3131: CB BLDG 313, ECO #1 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 1

** PROJECT OWNER SUMMARY - LEVEL 1 **

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	15,069	0	753	0	15,822	15822.22
CB BLDG 313, ECO #1	1.00 EA	15,069	0	753	0	15,822	15822.22

LABOR ID: R01 92 EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B UFB ID: NAT92A

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3131: CB BLDG 313, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:23:35

SUMMARY PAGE 2

[illegible]

LABOR ID: R01_92

EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B

UPB ID: NAT92A

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 14:23:35

PROJECT CB3131: CB BLDG 313, ECO #1 - ESOS Carlisle Barracks

INTERIM SUBMISSION

SUMMARY PAGE 3

** CONTRACTOR INDIRECT SUMMARY **

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	11,456	573	1,203	1,146	288	14,665	14664.62
EL Electrical Contractor	316	16	33	32	8	404	404.16

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 14:23:35

PROJECT CB3131: CB BLDG 313, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

		QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Removal & Resetting of Millwork					0.03	0.95	0.01	0.00	0.00	0.96
	815.00	LF	ULABF		27	774	6	0	0	780
Sills & Plates, 2x4 So Yel Pine					0.02	0.80	0.02	0.24	0.00	1.06
	355.00	BF	ACARD		8	284	7	87	0	378
Jamb Extensions					0.03	0.79	0.01	0.42	0.00	1.22
	533.00	LF	ULABF		15	421	3	226	0	650
2" Polyiso., R14.3 Rigid Insul.					0.01	0.26	0.00	0.90	0.00	1.16
	2636.00	SF	ACARA		19	685	7	2,375	0	3,067
4" Kraft Faced, R11 Fbgs Insul					0.01	0.30	0.00	0.14	0.00	0.44
	2584.00	SF	ACARA		22	768	7	356	0	1,131
1/2" Drywall, One Layer, One Face					0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)					30	1,057	11	486	0	2,396
For Taping, Spackling, And					21	761	8	73		
Std. 2" Z Furring, Galv.					2.09	74.50	0.72	28.09	0.00	103.31
	17.28	CLF	ACARA		36	1,287	12	485	0	1,785
Interior Roller Work					0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint					28	756	9	503	0	1,268
Electrical Work on Outlets & Switches					0.28	11.00	0.04	2.12	0.00	13.16
	24.00	EA	EELEB		7	264	1	51	0	316
Contract					212	7,059	70	4,642	0	11,771
CB BLDG 313, ECO #1					212	7,059	70	4,642	0	11,771

LABOR ID: R01_92

EQUIP ID: R60192

Currency in DOLLARS

CREW ID: NAT92B

UPB ID: NAT92A

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 14:23:35

PROJECT CB3131: CB BLDG 313, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 313

Building Name: *OFFICERS CLUB*

Date Prepared: 11 JAN 94

Estimator: *DJL*

Sheet 3 of 3

	BID ITEM WEATHERSTRIPPING/CAULKING
--	------------------------------------

[illegible]

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3133: CB BLDG 313, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:28:28

TITLE PAGE 1

CB BLDG 313, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 313, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/13/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3133: CB BLDG 313, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:28:28

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

		AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
01 General Contractor											
OVERHEAD	P			5.00							
HOME OFC	P			10.00							
PROFIT	C			8.65	0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P			2.00							

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3133: CB BLDG 313, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:28:28

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

*** END TABLE OF CONTENTS ***

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3133: CB BLDG 313, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:28:28

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00	EA	3,053	0	153	0	3,205	3205.41
CB BLDG 313, ECO #3	1.00	EA	3,053	0	153	0	3,205	3205.41

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 14:28:28

PROJECT CB3133: CB BLDG 313, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTITY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
----------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

Polyurethane Cmpd, 1/4"x1/4" Joint			4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	10.25	CLF ARFCA	48	1,705	11	98	0	1,814

Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	109.00	LF ACARB	8	286	3	72	0	360

Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	25.00	LF ACARB	5	187	2	21	0	211
Bulb								

Contract			61	2,179	15	191	0	2,385
----------	--	--	----	-------	----	-----	---	-------

CB BLDG 313, ECO #3			61	2,179	15	191	0	2,385
---------------------	--	--	----	-------	----	-----	---	-------

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3133: CB BLDG 313, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:28:28

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	61	2,179	15	191	0	2,385	2384.86
CB BLDG 313, ECO #3 OVERHEAD	1.00	EA	61	2,179	15	191	0	2,385	2384.86
								119	
SUBTOTAL								2,504	
HOME OFC								250	
SUBTOTAL								2,755	
PROFIT								238	
SUBTOTAL								2,993	
BOND								60	
TOTAL INCL INDIRECTS								3,053	
CONTINGENCY								153	
TOTAL INCL OWNER COSTS								3,205	

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3133: CB BLDG 313, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:28:28

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	2,385	119	250	238	60	3,053	3052.77

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 14:28:28

PROJECT CB3133: CB BLDG 313, ECO #3 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 318

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 318

Building Name: **QUARTERS 318**

Date Prepared: 11 JAN. 94

Estimator: K. STICK

Sheet 1 of 2

<div style="text-align: right;"> BID ITEM - WALL/ROOF INSULATION </div>	
--	--

[illegible]

* NOTE : QUANTITIES INCLUDE BOTH SIDES OF DBL. HOUSE.

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3181: CB BLDG 318, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 14:53:51

TITLE PAGE 1

CB BLDG 318, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 318, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 05/17/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3181: CB BLDG 318, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 14:53:51

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

		AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
01 General Contractor											
OVERHEAD	S		5.00	5.00							
HOME OFC	P		10.00								
PROFIT	S		8.66	5.00							
BOND	P		2.00								
02 Electrical Contractor											
OVERHEAD	P		5.00								
HOME OFC	P		10.00								
PROFIT	C		8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P		2.00								

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3181: CB BLDG 318, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 14:53:51

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3181: CB BLDG 318, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:53:51

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	9,239	0	462	0	9,701	9700.94
CB BLDG 318, ECO #1	1.00 EA	9,239	0	462	0	9,701	9700.94

Tue 17 May 1994

U.S. Army Corps of Engineers
 PROJECT CB3181: CB BLDG 318, ECO #1 - ESOS Carlisle Barracks
 PREFINAL SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:53:51

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	137	4,237	655	2,325	0	7,217	7217.26
CB BLDG 318, ECO #1	1.00 EA	137	4,237	655	2,325	0	7,217	7217.26
OVERHEAD							361	
SUBTOTAL							7,578	
HOME OFC							758	
SUBTOTAL							8,336	
PROFIT							722	
SUBTOTAL							9,058	
BOND							181	
TOTAL INCL INDIRECTS							9,239	
CONTINGENCY							462	
TOTAL INCL OWNER COSTS							9,701	

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3181: CB BLDG 318, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:53:51

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	7,217	361	758	722	181	9,239	9238.99

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 14:53:51

PROJECT CB3181: CB BLDG 318, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

PREFINAL SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY UOM CREW ID			MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract								
Blown-in Cell. Insul. R22			0.08	2.38	0.37	0.56	0.00	3.31
221.00 CF AASBD			17	526	81	124	0	731
Blown-in Cell. Insul. R11			0.05	1.66	0.26	1.17	0.00	3.09
1364.00 SF AASBD			73	2,267	351	1,590	0	4,208
Blown-in Cell. Insul. R19			0.03	0.88	0.14	0.37	0.00	1.38
1646.00 SF AASBD			47	1,444	223	611	0	2,277
Contract			137	4,237	655	2,325	0	7,217
CB BLDG 318, ECO #1			137	4,237	655	2,325	0	7,217

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 14:53:51

PROJECT CB3181: CB BLDG 318, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

[illegible]

933702

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3183: CB BLDG 318, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:48:27

TITLE PAGE 1

CB BLDG 318, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 318, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/13/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3183: CB BLDG 318, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:48:27

SETTINGS PAGE 1

**- CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3183: CB BLDG 318, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:48:27

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3183: CB BLDG 318, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:48:27

SUMMARY PAGE 1

** PROJECT OWNER SUMMARY - LEVEL 1 **

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	2,576	0	129	0	2,705	2705.05
CB BLDG 318, ECO #3	1.00 EA	2,576	0	129	0	2,705	2705.05

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3183: CB BLDG 318, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:48:27

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	51	1,812	14	187	0	2,013	2012.58
CB BLDG 318, ECO #3 OVERHEAD	1.00 EA	51	1,812	14	187	0	2,013 101	2012.58
SUBTOTAL HOME OFC							2,113 211	
SUBTOTAL PROFIT							2,325 201	
SUBTOTAL BOND							2,526 51	
TOTAL INCL INDIRECTS CONTNGENCY							2,576 129	
TOTAL INCL OWNER COSTS							2,705	

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3183: CB BLDG 318, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:48:27

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	2,013	101	211	201	51	2,576	2576.24

Thu 13 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB3183: CB BLDG 318, ECO #3 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 01. Contract

TIME 14:48:27

DETAILED ESTIMATE

DETAIL PAGE 1

		QUANTY	UOM	CREW	ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract											
Polyurethane Cmpd, 1/4"x1/4" Joint						4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows		7.54	CLF	ARFCA		35	1,255	8	72	0	1,334
Mtl Weatherstrip w/Neoprene Bulb											
For Head and Jamb		144.00	LF	ACARB		11	378	4	95	0	476
Mtl Weatherstrip for Door Bottom											
Surface Mounted w/Vinyl Bulb		24.00	LF	ACARB		5	180	2	20	0	202
Bulb											
Contract						51	1,812	14	187	0	2,013
CB BLDG 318, ECO #3						51	1,812	14	187	0	2,013

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 14:48:27

PROJECT CB3183: CB BLDG 318, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 321

Architectural Estimate

933702

[illegible]

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3211: CB BLDG 321, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 14:56:17

TITLE PAGE 1

CB BLDG 321, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 321, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 05/17/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3211: CB BLDG 321, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 14:56:17

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

		AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
01 General Contractor											
OVERHEAD	S		5.00	5.00							
HOME OFC	P		10.00								
PROFIT	S		8.66	5.00							
BOND	P		2.00								
02 Electrical Contractor											
OVERHEAD	P		5.00								
HOME OFC	P		10.00								
PROFIT	C		8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P		2.00								

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3211: CB BLDG 321, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

TIME 14:56:17

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3211: CB BLDG 321, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:56:17

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	3,174	0	159	0	3,333	3332.78
CB BLDG 321, ECO #1	1.00 EA	3,174	0	159	0	3,333	3332.78

Tue 17 May 1994

U.S. Army Corps of Engineers
 PROJECT CB3211: CB BLDG 321, ECO #1 - ESOS Carlisle Barracks
 PREFINAL SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:56:17

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	57	1,773	274	432	0	2,480	2479.51
CB BLDG 321, ECO #1 OVERHEAD	1.00 EA	57	1,773	274	432	0	2,480 124	2479.51
SUBTOTAL HOME OFC							2,603 260	
SUBTOTAL PROFIT							2,864 248	
SUBTOTAL BOND							3,112 62	
TOTAL INCL INDIRECTS CONTNGENCY							3,174 159	
TOTAL INCL OWNER COSTS							3,333	

Tue 17 May 1994

U.S. Army Corps of Engineers
PROJECT CB3211: CB BLDG 321, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:56:17

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	2,480	124	260	248	62	3,174	3174.08

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 14:56:17

PROJECT CB3211: CB BLDG 321, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

PREFINAL SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

Blown-in Cell. Insul. R22			0.08	2.38	0.37	0.56	0.00	3.31
	714.00 CF	AASBD	55	1,699	263	401	0	2,363

Blown-in Cell. Insul. R19			0.03	0.88	0.14	0.37	0.00	1.38
	84.00 SF	AASBD	2	74	11	31	0	116

Contract			57	1,773	274	432	0	2,480
----------	--	--	----	-------	-----	-----	---	-------

CB BLDG 321, ECO #1			57	1,773	274	432	0	2,480
---------------------	--	--	----	-------	-----	-----	---	-------

Tue 17 May 1994

U.S. Army Corps of Engineers

TIME 14:56:17

PROJECT CB3211: CB BLDG 321, ECO #1 - ESOS Carlisle Barracks
PREFINAL SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

[illegible]

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3213: CB BLDG 321, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:57:31

TITLE PAGE 1

CB BLDG 321, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 321, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/13/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3213: CB BLDG 321, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:57:31

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3213: CB BLDG 321, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 14:57:31

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3213: CB BLDG 321, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 14:57:31

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00	EA	1,207	0	60	0	1,267	1267.00
CB BLDG 321, ECO #3	1.00	EA	1,207	0	60	0	1,267	1267.00

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3213: CB BLDG 321, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 14:57:31

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	24	866	6	71	0	943	942.66
CB BLDG 321, ECO #3 OVERHEAD	1.00 EA	24	866	6	71	0	943	942.66
							47	
SUBTOTAL							990	
HOME OFC							99	
SUBTOTAL							1,089	
PROFIT							94	
SUBTOTAL							1,183	
BOND							24	
TOTAL INCL INDIRECTS							1,207	
CONTINGENCY							60	
TOTAL INCL OWNER COSTS							1,267	

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB3213: CB BLDG 321, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 14:57:31

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	943	47	99	94	24	1,207	1206.67

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 14:57:31

PROJECT CB3213: CB BLDG 321, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

		QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Polyurethane Cmpd, 1/4"x1/4" Joint					4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows					20	724	4	41	0	770
4.35 CLF ARFCA										
Mtl Weatherstrip w/Neoprene Bulb					0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb					3	97	1	24	0	122
37.00 LF ACARB										
Mtl Weatherstrip for Door Bottom					0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb					1	45	0	5	0	51
6.00 LF ACARB										
Bulb										
Contract					24	866	6	71	0	943
CB BLDG 321, ECO #3					24	866	6	71	0	943

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 14:57:31

PROJECT CB3213: CB BLDG 321, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 330

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 330

Building Name: DPW

Date Prepared: 29 DEC. 93

Estimator: K. STICK

Sheet 1 of 1

BID ITEM - WEATHERSTRIPPING & CAULKING

[illegible]

Wed 29 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB3303: CB BLDG 330, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 13:07:54

TITLE PAGE 1

CB BLDG 330, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 330, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 12/29/93

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Wed 29 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB3303: CB BLDG 330, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 13:07:54

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Wed 29 Dec 1993

U.S. Army Corps of Engineers

TIME 13:07:54

PROJECT CB3303: CB BLDG 330, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

*** END TABLE OF CONTENTS ***

Wed 29 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB3303: CB BLDG 330, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 13:07:54

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	1,642	0	82	0	1,725	1724.61
CB BLDG 330, ECO #3	1.00 EA	1,642	0	82	0	1,725	1724.61

Wed 29 Dec 1993

U.S. Army Corps of Engineers
 PROJECT CB3303: CB BLDG 330, ECO #3 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 13:07:54

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	33	1,187	8	88	0	1,283	1283.13
CB BLDG 330, ECO #3	1.00 EA	33	1,187	8	88	0	1,283	1283.13
OVERHEAD							64	
SUBTOTAL							1,347	
HOME OFC							135	
SUBTOTAL							1,482	
PROFIT							128	
SUBTOTAL							1,610	
BOND							32	
TOTAL INCL INDIRECTS							1,642	
CONTNGENCY							82	
TOTAL INCL OWNER COSTS							1,725	

Wed 29 Dec 1993

U.S. Army Corps of Engineers
PROJECT CB3303: CB BLDG 330, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 13:07:54

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	1,283	64	135	128	32	1,642	1642.49

Wed 29 Dec 1993

U.S. Army Corps of Engineers

TIME 13:07:54

PROJECT CB3303: CB BLDG 330, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

Polyurethane Cmpd, 1/4"x1/4" Joint			4.65	166.39	1.03	9.54	0.00	176.96
Caulking on Ext. Doors & Windows	6.33	CLF ARFCA	29	1,053	7	60	0	1,120

Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb on Exterior Doors	34.00	LF ACARB	3	89	1	22	0	112

Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	6.00	LF ACARB	1	45	0	5	0	51

Contract			33	1,187	8	88	0	1,283
----------	--	--	----	-------	---	----	---	-------

CB BLDG 330, ECO #3			33	1,187	8	88	0	1,283
---------------------	--	--	----	-------	---	----	---	-------

Wed 29 Dec 1993

U.S. Army Corps of Engineers

TIME 13:07:54

PROJECT CB3303: CB BLDG 330, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 400
Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 400	Building Name: FIRE HALL	
Date Prepared: 11 JAN. 94	Estimator: K. STICK	Sheet 1 of 3
BID ITEM - WALL / ROOF INSULATION		
Description	Quantity	Unit Measurement
DIV. 02 REMOVAL & RESETTNG OF EXIST.		
MILLWORK (BASE & CASING)	1613	L.F.
DIV. 06 06111 4201 2x4 WOOD FRAMING		
AROUND WINDOW & DOOR OPENINGS	691	B.F.
DIV. 06 1x3 PINE JAMB EXTENSIONS	1037	L.F.
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD.		
R = 14.3 (WALL INSUL.)	5905	S.F.
DIV. 07 07210 1004 INSTALL 6" KRAFT FACED		
FIBERGLASS INSUL. R = 19.0		
(BETWEEN ROOF RAFTERS)	4922	S.F.
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL	5905	S.F.
(INCLUDE 4001)		
DIV. 09 INSTALL STD. 2" 'Z' FURRING @ 24" O.C.		
BETWEEN 2" RIGID INSUL. BD.	38.06	C.L.F.

[illegible]

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4001: CB BLDG 400, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:08:22

TITLE PAGE 1

CB BLDG 400, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 400, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/13/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4001: CB BLDG 400, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:08:22

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	S	5.00	5.00							
HOME OFC	P	10.00								
PROFIT	S	8.66	5.00							
BOND	P	2.00								

02 Electrical Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 15:08:22

PROJECT CB4001: CB BLDG 400, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4001: CB BLDG 400, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 15:08:22

SUMMARY PAGE 1

	QUANTITY	VOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00	EA	33,485	0	1,674	0	35,159	35159.00
CB BLDG 400, ECO #1	1.00	EA	33,485	0	1,674	0	35,159	35159.00

Thu 13 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB4001: CB BLDG 400, ECO #1 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 15:08:22

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	461	15,407	152	10,599	0	26,157	26157.49
CB BLDG 400, ECO #1	1.00 EA	461	15,407	152	10,599	0	26,157	26157.49
OVERHEAD							1,308	
SUBTOTAL							27,465	
HOME OFC							2,747	
SUBTOTAL							30,212	
PROFIT							2,616	
SUBTOTAL							32,828	
BOND							657	
TOTAL INCL INDIRECTS							33,485	
CONTNGENCY							1,674	
TOTAL INCL OWNER COSTS							35,159	

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4001: CB BLDG 400, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 15:08:22

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	25,154	1,258	2,641	2,516	631	32,201	32200.81
EL Electrical Contractor	1,003	50	105	100	25	1,284	1283.95

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 15:08:22

PROJECT CB4001: CB BLDG 400, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

	QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract									
Removal & Resetting of Millwork				0.03	0.95	0.01	0.00	0.00	0.96
	1613.00	LF	ULABF	53	1,532	11	0	0	1,544
Sills & Plates, 2x4 So Yel Pine				0.02	0.80	0.02	0.24	0.00	1.06
	691.00	BF	ACARD	16	553	14	168	0	735
Jamb Extensions				0.03	0.79	0.01	0.42	0.00	1.22
	1037.00	LF	ULABF	28	819	6	440	0	1,265
2" Polyiso., R14.3 Rigid Insul.				0.01	0.26	0.00	0.90	0.00	1.17
	5905.00	SF	ACARA	44	1,562	15	5,320	0	6,898
6-1/4" Kraft Faced R19 Fbgs Insul				0.01	0.30	0.00	0.22	0.00	0.52
	4922.00	SF	ACARA	41	1,463	14	1,096	0	2,572
1/2" Drywall, One Layer, One Face				0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)	5905.00	SF	ACARB	66	2,369	24	1,089	0	5,368
For Taping, Spackling, And				48	1,706	18	163		
Ed. 2" Z Furring, Galv.				2.09	74.50	0.72	28.09	0.00	103.31
	39.06	CLF	ACARA	30	2,836	27	1,069	0	3,932
Interior Roller Work				0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint	5905.00	SF	APTRA	63	1,694	19	1,127	0	2,840
Electrical Work on Outlets & Switches				0.28	11.00	0.04	2.12	0.00	13.16
	60.00	EA	EELEB	17	660	2	127	0	789
Electrical Work on 200 A Disc. Switch				5.38	213.02	0.69	0.00	0.00	213.71
	1.00	EA	EELEB	5	213	1	0	0	214
Contract				461	15,407	152	10,599	0	26,157
CB BLDG 400, ECO #1				461	15,407	152	10,599	0	26,157

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 15:08:22

PROJECT CB4001: CB BLDG 400, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

[illegible]

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4003: CB BLDG 400, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:11:35

TITLE PAGE 1

CB BLDG 400, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 400, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/13/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4003: CB BLDG 400, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 15:11:35

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
--------	-----	-------	------	------	------	--------	--------	--------	--------

01 General Contractor

OVERHEAD	P	5.00							
HOME OFC	P	10.00							
PROFIT	C	8.65	0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00							

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 15:11:35

PROJECT CB4003: CB BLDG 400, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4003: CB BLDG 400, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 15:11:35

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00	EA	3,374	0	169	0	3,543	3542.71
CB BLDG 400, ECO #3	1.00	EA	3,374	0	169	0	3,543	3542.71

Thu 13 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB4003: CB BLDG 400, ECO #3 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 ** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 15:11:35

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	67	2,389	18	229	0	2,636	2635.81
CB BLDG 400, ECO #3	1.00 EA	67	2,389	18	229	0	2,636	2635.81
OVERHEAD							132	
SUBTOTAL							2,768	
HOME OFC							277	
SUBTOTAL							3,044	
PROFIT							263	
SUBTOTAL							3,308	
BOND							66	
TOTAL INCL INDIRECTS							3,374	
CONTINGENCY							169	
TOTAL INCL OWNER COSTS							3,543	

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4003: CB BLDG 400, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 15:11:35

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	2,636	132	277	263	66	3,374	3374.01

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 15:11:35

PROJECT CB4003: CB BLDG 400, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01, Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

Polyurethane Cmpd, 1/4"x1/4" Joint			4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	10.37	CLF ARFCA	48	1,725	11	99	0	1,835

Mtl Weatherstrip w/Neoprene Bulb			0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	153.00	LF ACARB	11	401	4	101	0	506

Mtl Weatherstrip for Door Bottom			0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	35.00	LF ACARB	7	262	3	30	0	295
Bulb								

Contract			67	2,389	18	229	0	2,636
----------	--	--	----	-------	----	-----	---	-------

CB BLDG 400, ECO #3			67	2,389	18	229	0	2,636
---------------------	--	--	----	-------	----	-----	---	-------

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 15:11:35

PROJECT CB4003: CB BLDG 400, ECO #3 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 420

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. **420** Building Name: **HEADQUARTERS COMPANY**

Date Prepared: **7 JAN 94** Estimator: **DJL** Sheet **1** of **3**

BID ITEM WALL / ROOF INSULATION

Description	Quantity	Unit Measurement
DIV 06 0611 4201 2x4 WOOD FRAMING @ WINDOW & DOOR OPENINGS	1,559	B.F.
DIV.07 INSTALL 2" RIGID POLYISO. INSUL. BD. R=14.3 WALL INSULATION	11,986	S.F.
DIV.07 07210 1017 INSTALL 6" UNFACED FIBERGLASS INSUL. R=19.0 (ROOF INSUL)	6,680	S.F.
DIV.09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	11,986	S.F.
DIV.09 INSTALL STD 2" 'Z' FURRING @ 24" O.C. ON EXTERIOR WALLS.	53.16	C.L.F.
DIV.09 INSTALL 4" VINYL BASE	443	L.F.
DIV.09 09920 1221 PAINTING 1/2" DRYWALL	11,986	S.F.
DIV. 16 ELECT. WORK ON OUTLETS & SWITCHES	82	EA.

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 420

Building Name: HEADQUARTERS COMPANY

Date Prepared: 7 JAN 94

Estimator: *DJL*

Sheet 2 of 3

BID ITEM WALL / ROOF INSULATION	
---------------------------------	--

[illegible]

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4201: CB BLDG 420, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:13:37

TITLE PAGE 1

CB BLDG 420, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 420, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/10/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4201: CB BLDG 420, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:13:37

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	S	5.00	5.00							
HOME OFC	P	10.00								
PROFIT	S	8.66	5.00							
BOND	P	2.00								

02 Electrical Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4201: CB BLDG 420, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:13:37

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4201: CB BLDG 420, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 16:13:37

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	55,186	0	2,759	0	57,946	57945.59
CB BLDG 420, ECO #1	1.00 EA	55,186	0	2,759	0	57,946	57945.59

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4201: CB BLDG 420, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 16:13:37

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	688	23,410	247	19,453	0	43,110	43110.18
CB BLDG 420, ECO #1 OVERHEAD	1.00	EA	688	23,410	247	19,453	0	43,110 2,156	43110.18
SUBTOTAL								45,266	
HOME OFC								4,527	
SUBTOTAL								49,792	
PROFIT								4,312	
SUBTOTAL								54,104	
BOND								1,082	
TOTAL INCL INDIRECTS								55,186	
CONTNGENCY								2,759	
TOTAL INCL OWNER COSTS								57,946	

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4201: CB BLDG 420, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 16:13:37

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	41,778	2,089	4,387	4,179	1,049	53,481	53480.74
EL Electrical Contractor	1,332	67	140	133	33	1,706	1705.53

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 16:13:37

PROJECT CB4201: CB BLDG 420, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTITY UOM CREW ID			MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract								
Sills & Plates, 2x4 So Yel Pine			0.02	0.80	0.02	0.24	0.00	1.06
1559.00 BF ACARD			35	1,248	31	380	0	1,658
2" Polyiso., R14.3 Rigid Insul.			0.01	0.26	0.00	0.90	0.00	1.16
11986 SF ACARA			87	3,116	30	10,799	0	13,946
1/2" Drywall, One Layer, One Face			0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)	11986 SF ACARB		135	4,808	49	2,210	0	10,897
For Taping, Spackling, And			97	3,462	36	331		
6" Unfaced Batt, R19 Fbgs Insul			0.01	0.30	0.00	0.21	0.00	0.51
6680.00 SF ACARA			56	1,985	19	1,416	0	3,420
Std. 2" Z Furring, Galv.			2.09	74.50	0.72	28.09	0.00	103.31
53.16 CLF ACARA			111	3,961	38	1,493	0	5,492
4" Vinyl Base			0.02	0.61	0.00	0.74	0.00	1.36
443.00 LF APAPA			10	270	1	329	0	600
Interior Roller Work			0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint	11986 SF APTRA		129	3,439	39	2,287	0	5,764
Electrical Work on Outlets & Switches			0.28	11.00	0.04	2.12	0.00	13.16
82.00 EA EELEB			23	902	3	174	0	1,079
Electrical Work on Fire Alarm Pull Stations			0.82	32.50	0.11	2.12	0.00	34.73
1.00 EA EELEB			1	33	0	2	0	35
Electrical Work on Fire Alarm Bells			0.82	32.50	0.11	2.12	0.00	34.73
1.00 EA EELEB			1	33	0	2	0	35
Electrical Work on TV Outlets			0.28	11.00	0.04	2.12	0.00	13.16
14.00 EA EELEB			4	154	0	30	0	184
Contract			688	23,410	247	19,453	0	43,110
CB BLDG 420, ECO #1			688	23,410	247	19,453	0	43,110

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 16:13:37

PROJECT CB4201: CB BLDG 420, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

*** END OF ERROR REPORT ***

CARLISLE BARRACKS ENERGY STUDY

Individual Building Material Take Off Worksheet

Building No. 420

Building Name: HEADQUARTERS COMPANY

Date Prepared:

JAN 94

Estimator: DJL

Sheet 3 of 3

BID ITEM VESTIBULES	
1	1.00
2	1.00
3	1.00
4	1.00
5	1.00
6	1.00
7	1.00
8	1.00
9	1.00
10	1.00
11	1.00
12	1.00
13	1.00
14	1.00
15	1.00
16	1.00
17	1.00
18	1.00
19	1.00
20	1.00
21	1.00
22	1.00
23	1.00
24	1.00
25	1.00
26	1.00
27	1.00
28	1.00
29	1.00
30	1.00
31	1.00
32	1.00
33	1.00
34	1.00
35	1.00
36	1.00
37	1.00
38	1.00
39	1.00
40	1.00
41	1.00
42	1.00
43	1.00
44	1.00
45	1.00
46	1.00
47	1.00
48	1.00
49	1.00
50	1.00
51	1.00
52	1.00
53	1.00
54	1.00
55	1.00
56	1.00
57	1.00
58	1.00
59	1.00
60	1.00
61	1.00
62	1.00
63	1.00
64	1.00
65	1.00
66	1.00
67	1.00
68	1.00
69	1.00
70	1.00
71	1.00
72	1.00
73	1.00
74	1.00
75	1.00
76	1.00
77	1.00
78	1.00
79	1.00
80	1.00
81	1.00
82	1.00
83	1.00
84	1.00
85	1.00
86	1.00
87	1.00
88	1.00
89	1.00
90	1.00
91	1.00
92	1.00
93	1.00
94	1.00
95	1.00
96	1.00
97	1.00
98	1.00
99	1.00
100	1.00

[illegible]

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB420E: CB BLDG 420, ECO #E - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:24:14

TITLE PAGE 1

CB BLDG 420, ECO #E
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 420, Vestibule
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/10/94

M C A C E S G O L D E D I T I O N
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB420E: CB BLDG 420, ECO #E - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:24:14

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 16:24:14

PROJECT CB420E: CB BLDG 420, ECO #E - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

*** END TABLE OF CONTENTS ***

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB420E: CB BLDG 420, ECO #E - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 16:24:14

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	10,132	0	507	0	10,639	10638.87
CB BLDG 420, ECO #E	1.00 EA	10,132	0	507	0	10,639	10638.87

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB420E: CB BLDG 420, ECO #E - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 16:24:14

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	145	5,504	54	2,357	0	7,915	7915.43
CB BLDG 420, ECO #E OVERHEAD	1.00 EA	145	5,504	54	2,357	0	7,915 396	7915.43
SUBTOTAL							8,311	
HOME OFC							831	
SUBTOTAL							9,142	
PROFIT							791	
SUBTOTAL							9,934	
BOND							199	
TOTAL INCL INDIRECTS							10,132	
CONTINGENCY							507	
TOTAL INCL OWNER COSTS							10,639	

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB420E: CB BLDG 420, ECO #E - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 16:24:14

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	7,915	396	831	791	199	10,132	10132.26

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 16:24:14

PROJECT CB420E: CB BLDG 420, ECO #E - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

3'x7'Wide Style Al Door Unit			8.00	312.24	3.07	453.68	0.00	768.99
Commercial (Rear Ent. Vest.)	2.00 EA	SIWSB	16	624	6	907	0	1,538

1/4" Thk Clear Float Glass			0.15	1.89	0.02	4.24	0.00	6.15
(Rear Ent. Vest.)	42.00 SF	AGLAB	6	80	1	178	0	258

8'x10' Front Entrance Vestibule			1.54	60.00	0.59	15.90	0.00	76.49
	80.00 SF	SIWSB	123	4,800	47	1,272	0	6,119

Contract			145	5,504	54	2,357	0	7,915
----------	--	--	-----	-------	----	-------	---	-------

CB BLDG 420, ECO #E			145	5,504	54	2,357	0	7,915
---------------------	--	--	-----	-------	----	-------	---	-------

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 16:24:14

PROJECT CB420E: CB BLDG 420, ECO #E - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 452

Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 452		Building Name: CHAPEL	
Date Prepared: 5 JAN. 94	Estimator: K. STICK	Sheet 1 of 3	
BID ITEM - WALL / ROOF INSULATION			
Description	Quantity	Unit Measurement	
DIV. 02 REMOVAL & RESETT'G OF EXIST'G.			
MILLWORK (CASING & COVE MOLD'G)	3987	L.F.	
DIV. 06 06111 4201 2x4 WOOD FRAMING			
AROUND WINDOW & DOOR OPENINGS	1591	B.F.	
DIV. 06 1x3 PINE JAMB EXTENSIONS	1591	L.F.	
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD.			
R = 14.3 (WALL INSUL.)	11,172	S.F.	
DIV. 07 07210 1017 INSTALL 6" UNFACED			
FIBERGLASS INSUL. R = 19.0			
(ROOF INSUL. - ADMIN. WING, ACTIVITY &			
ASSEMBLY WING & CLASSROOM WING)	11,602	S.F.	
DIV. 07 INSTALL 1" RIGID POLYISO. INSUL. BD.			
(R = 7.2) TO EXIST'G WOOD FURR'G LOCATED			
BETWEEN WOOD PURLINS - NAVE &	4,324	S.F.	
NARTHEX (ROOF INSUL.)			
(INCLUDE 4005)			

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 452	Building Name: CHAPEL	
Date Prepared: 5 JAN. 94	Estimator: K. STICK	Sheet 2 of 3
BID ITEM - WALL / ROOF INSULATION		
Description	Quantity	Unit Measurement
DIV. 07 07210 1004 INSTALL 6" KRAFT FACED FIBERGLASS INSUL. BETWEEN RAFTERS R = 19.0 (ROOF INSUL. - EQUIP. / MECH. RM.)	759	S.F.
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	11,172	S.F.
DIV. 09 INSTALL STD. 2" Z' FURR'G @ 24" O.C. BETWEEN 2" RIGID INSUL. BD.	71.15	C.L.F.
DIV. 09 09920 1221 PAINT'G 1/2" DRYWALL	11,172	S.F.
DIV. 09 09920 1304 PAINT'G INT. WOOD TRIM	1591	L.F.
DIV. 09 CEMENT 12"x12" ACOUST. TILE TO 1" RIGID INSUL. BD. @ NAVE/NARTHEX	4,324	S.F.
DIV. 16 ELEC. WORK ON OUTLETS & SWITCHES	140	EA.
DIV. 16 ELEC. WORK ON WALL MTD. LIGHT FIXT.	5	EA.
DIV. 16 ELEC. WORK ON FIRE ALARM PULL STATIONS	10	EA.
DIV. 16 ELEC. WORK ON FIRE ALARM BELLS	2	EA.

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4521: CB BLDG 452, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:54:31

TITLE PAGE 1

CB BLDG 452, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 452, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/10/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4521: CB BLDG 452, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:54:31

SETTINGS PAGE 1

- CONTRACTOR SETTINGS -

		AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
01 General Contractor											
OVERHEAD	S		5.00	5.00							
HOME OFC	P		10.00								
PROFIT	S		8.66	5.00							
BOND	P		2.00								
02 Electrical Contractor											
OVERHEAD	P		5.00								
HOME OFC	P		10.00								
PROFIT	C		8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P		2.00								

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 16:54:31

PROJECT CB4521: CB BLDG 452, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4521: CB BLDG 452, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 16:54:31

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	83,395	0	4,170	0	87,564	87564.40
CB BLDG 452, ECO #1	1.00 EA	83,395	0	4,170	0	87,564	87564.40

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4521: CB BLDG 452, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 16:54:31

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	1,137	37,907	374	26,865	0	65,146	65145.91
CB BLDG 452, ECO #1 OVERHEAD	1.00	EA	1,137	37,907	374	26,865	0	65,146 3,257	65145.91
SUBTOTAL HOME OFC								68,403 6,840	
SUBTOTAL PROFIT								75,244 6,516	
SUBTOTAL BOND								81,759 1,635	
TOTAL INCL INDIRECTS CONTNGENCY								83,395 4,170	
TOTAL INCL OWNER COSTS								87,564	

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4521: CB BLDG 452, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 16:54:31

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	62,709	3,135	6,584	6,272	1,574	80,275	80274.90
EL Electrical Contractor	2,437	122	256	244	61	3,120	3119.76

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 16:54:31

PROJECT CB4521: CB BLDG 452, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

	QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract									
Removal & Resetting of Millwork				0.03	0.95	0.01	0.00	0.00	0.96
	3987.00	LF	ULABF	130	3,788	28	0	0	3,816
Sills & Plates, 2x4 So Yel Pine				0.02	0.80	0.02	0.24	0.00	1.06
	1591.00	BF	ACARD	36	1,273	31	388	0	1,692
Jamb Extensions				0.03	0.79	0.01	0.42	0.00	1.22
	1591.00	LF	ULABF	43	1,257	9	675	0	1,941
2" Polyiso., R14.3 Rigid Insul.				0.01	0.26	0.00	0.90	0.00	1.16
	11172	SF	ACARA	81	2,905	28	10,066	0	12,999
6" Unfaced Batt, R19 Fbgs Insul				0.01	0.30	0.00	0.21	0.00	0.51
	11602	SF	ACARA	97	3,448	33	2,460	0	5,941
1" Polyiso., R7.2 Rigid Insul.				0.01	0.24	0.00	0.66	0.00	0.90
	4324.00	SF	ACARA	29	1,038	10	2,842	0	3,890
6-1/4" Kraft Faced R19 Fbgs Insul				0.01	0.30	0.00	0.22	0.00	0.52
	759.00	SF	ACARA	6	226	2	169	0	397
1/2" Drywall, One Layer, One Face				0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)	11172	SF	ACARB	126	4,482	46	2,060	0	10,157
For Taping, Spackling, And				90	3,227	33	309		
Std. 2" Z Furring, Galv.				2.09	74.50	0.72	28.09	0.00	103.31
	71.15	CLF	ACARA	149	5,301	51	1,999	0	7,351
Interior Roller Work				0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint	11172	SF	APTRA	120	3,205	36	2,132	0	5,373
Paint Int Wd Trim, 1 Prime, 2 Paint				0.04	1.14	0.01	0.08	0.00	1.23
Enamel Primer, Alkyd or Latex Pnt	1591.00	LF	APTRA	68	1,806	20	135	0	1,962
12"x12"x5/8" Vnyl Face Acous Tile				0.03	0.89	0.01	0.76	0.00	1.66
Mineral Fiber Ceiling Tile	4324.00	SF	ACARA	108	3,855	37	3,300	0	7,192
Electrical Work on Outlets & Switches				0.28	11.00	0.04	2.12	0.00	13.16
	140.00	EA	EELEB	39	1,540	5	297	0	1,842
Electrical Work on Wall Mounted Light Fixtures				0.93	33.50	0.12	2.12	0.00	35.74
	5.00	EA	EELEF	5	168	1	11	0	179
Electrical Work on Fire Alarm Pull Stations				0.82	32.50	0.11	2.12	0.00	34.73
	10.00	EA	EELEB	8	325	1	21	0	347
Electrical Work on Fire Alarm Bells				0.82	32.50	0.11	2.12	0.00	34.72
	2.00	EA	EELEB	2	65	0	4	0	69

LABOR ID: R01_92

EQUIP ID: RG0192

Currency in DOLLARS

CREW ID: NAT92B

UPB ID: NAT92A

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 16:54:31

PROJECT CB4521: CB BLDG 452, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 2

01. Contract

QUANTY	UOM	CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
--------	-----	---------	--------	-------	----------	----------	-------	------------

Contract

1,137	37,907	374	26,865	0	65,146
-------	--------	-----	--------	---	--------

CB BLDG 452, ECO #1

1,137	37,907	374	26,865	0	65,146
-------	--------	-----	--------	---	--------

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 16:54:31

PROJECT CB4521: CB BLDG 452, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

[illegible]

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4523: CB BLDG 452, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:58:16

TITLE PAGE 1

CB BLDG 452, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 452, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/10/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4523: CB BLDG 452, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:58:16

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 16:58:16

PROJECT CB4523: CB BLDG 452, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4523: CB BLDG 452, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:58:16

SUMMARY PAGE 1

** PROJECT OWNER SUMMARY - LEVEL 1 **

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	7,359	0	368	0	7,727	7726.53
CB BLDG 452, ECO #3	1.00 EA	7,359	0	368	0	7,727	7726.53

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4523: CB BLDG 452, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 16:58:16

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	147	5,242	38	469	0	5,749	5748.61
CB BLDG 452, ECO #3	1.00	EA	147	5,242	38	469	0	5,749	5748.61
OVERHEAD								287	
SUBTOTAL								6,036	
HOME OFC								604	
SUBTOTAL								6,640	
PROFIT								575	
SUBTOTAL								7,214	
BOND								144	
TOTAL INCL INDIRECTS								7,359	
CONTINGENCY								368	
TOTAL INCL OWNER COSTS								7,727	

Mon 10 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB4523: CB BLDG 452, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 16:58:16

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	5,749	287	604	575	144	7,359	7358.60

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 16:58:16

PROJECT CB4523: CB BLDG 452, ECO #3 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

		QUANTY	UOM	CREW	ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract											
Polyurethane Cmpd, 1/4"x1/4" Joint						4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows						111	3,972	25	228	0	4,224
		23.87	CLF	ARFCA							
Mtl Weatherstrip w/Neoprene Bulb						0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb						20	708	7	177	0	893
		270.00	LF	ACARB							
Mtl Weatherstrip for Door Bottom						0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb						16	562	6	64	0	632
		75.00	LF	ACARB							
Bulb											
Contract						147	5,242	38	469	0	5,749
CB BLDG 452, ECO #3						147	5,242	38	469	0	5,749

Mon 10 Jan 1994

U.S. Army Corps of Engineers

TIME 16:58:16

PROJECT CB4523: CB BLDG 452, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

Building 901
Architectural Estimate

933702

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 901	Building Name: GOLF HOUSE	
Date Prepared: 10 JAN. 94	Estimator: K. STICK	Sheet 1 of 4
BID ITEM - WALL / ROOF INSULATION		
Description	Quantity	Unit Measurement
DIV. 02 REMOVAL & RESETTNG OF EXIST. MILLWORK (CASING)	763	L.F.
DIV. 06 06111 4201 2X4 WOOD FRAMING AROUND WINDOW & DOOR OPENINGS	509	B.F.
DIV. 06 1x3 PINE JAMB EXTENSIONS	763	L.F.
DIV. 07 INSTALL 2" RIGID POLYISO. INSUL. BD. R=14.3 (WALL INSUL.)	2900	S.F.
DIV. 07 INSTALL 3" RIGID POLYISO. INSUL. BD. w/ 7/16" APA RATED OSB ON TOP SIDE. R=19.3 (ROOF INSUL. - LOUNGE AREA)	1494	S.F.
DIV. 07 BLOWN-IN CELLULOSE INSUL. - 4"± BETWEEN CEIL. JOISTS R=11.0	1400	S.F.
DIV. 09 09260 1002 INSTALL 1/2" DRYWALL (INCLUDE 4001)	2900	S.F.
DIV. 09 INSTALL STD. 2" 'Z' FURR'G @ 24" O.C. BETWEEN 2" RIGID INSUL. BD.	20.56	C.L.F.

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 901

Building Name: GOLF HOUSE

Date Prepared: 10 JAN. 94

Estimator: K. STICK

Sheet 2 of 4

BID ITEM - WALL / ROOF INSULATION

Description	Quantity	Unit Measurement
DIV. 09 INSTALL 4" VINYL COVE BASE	424	L.F.
DIV. 09 09920 1221 PAINTG 1/2" DRYWALL	2900	S.F.
DIV. 07 INSTALL 15# ROOF FELT (LOUNGE)	15	S.Q.
DIV. 07 INSTALL ASPHALT SHINGLES (LOUNGE)	15	S.Q.
DIV. 07 INSTALL ALUM. DRIP EDGE ON LOUNGE ROOF	120	L.F.
DIV. 16 ELEC. WORK ON OUTLETS & SWITCHES	18	EA.
DIV. 16 ELEC. WORK ON FIRE ALARM PULL STATIONS	8	EA
DIV. 16. ELEC. WORK ON FIRE ALARM BELLS	4	EA.

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9011: CB BLDG 901, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:21:08

TITLE PAGE 1

CB BLDG 901, ECO #1
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 901, Wall & Roof Insul.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/13/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9011: CB BLDG 901, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:21:08

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	S	5.00	5.00							
HOME OFC	P	10.00								
PROFIT	S	8.66	5.00							
BOND	P	2.00								

02 Electrical Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.66		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 16:21:08

PROJECT CB9011: CB BLDG 901, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....1
PROJECT DIRECT SUMMARY - LEVEL 1.....2
CONTRACTOR INDIRECT SUMMARY.....3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9011: CB BLDG 901, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 16:21:08

SUMMARY PAGE 1

	QUANTITY	UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00	EA	23,687	0	1,184	0	24,871	24871.37
CB BLDG 901, ECO #1	1.00	EA	23,687	0	1,184	0	24,871	24871.37

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9011: CB BLDG 901, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 16:21:08

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	276	9,084	123	9,297	0	18,504	18503.73
CB BLDG 901, ECO #1	1.00 EA	276	9,084	123	9,297	0	18,504	18503.73
OVERHEAD							925	
SUBTOTAL							19,429	
HOME OFC							1,943	
SUBTOTAL							21,372	
PROFIT							1,851	
SUBTOTAL							23,223	
BOND							464	
TOTAL INCL INDIRECTS							23,687	
CONTNGENCY							1,184	
TOTAL INCL OWNER COSTS							24,871	

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9011: CB BLDG 901, ECO #1 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 16:21:08

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	17,850	893	1,874	1,785	448	22,851	22850.51
EL Electrical Contractor	653	33	69	65	16	837	836.50

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 16:21:08

PROJECT CB9011: CB BLDG 901, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

	QUANTY	UOM	CREW	ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract										
Removal & Resetting of Millwork					0.03	0.95	0.01	0.00	0.00	0.96
	763.00	LF	ULABF		25	725	5	0	0	730
Sills & Plates, 2x4 So Yel Pine					0.02	0.80	0.02	0.24	0.00	1.06
	509.00	BF	ACARD		11	407	10	124	0	541
Jamb Extensions					0.03	0.79	0.01	0.42	0.00	1.22
	763.00	LF	ULABF		21	603	5	324	0	931
2" Polyiso., R14.3 Rigid Insul.					0.01	0.26	0.00	0.90	0.00	1.16
	2900.00	SF	ACARA		21	754	7	2,613	0	3,374
3" Polyiso., R19.3 Rigid Insul.					0.01	0.22	0.00	1.47	0.00	1.70
	1494.00	SF	APLAD		12	336	6	2,201	0	2,543
Blown-in Cell. Insul. R11					0.01	0.17	0.03	0.85	0.00	1.04
	1400.00	SF	AASED		8	238	37	1,187	0	1,462
1/2" Drywall, One Layer, One Face					0.02	0.69	0.01	0.21	0.00	0.91
On Metal Studs or Furring, (13mm)	2900.00	SF	ACARB		33	1,163	12	535	0	2,636
or Taping, Spackling, And					23	838	9	80		
Std. 2" Z Furring, Galv.					2.09	74.50	0.72	28.09	0.00	103.31
	20.56	CLF	ACARA		43	1,532	15	578	0	2,124
4" Vinyl Base					0.02	0.61	0.00	0.74	0.00	1.36
	424.00	LF	APAPA		10	259	1	315	0	575
Interior Roller Work					0.01	0.29	0.00	0.19	0.00	0.48
One Coat Primer-Two Coats Paint	2900.00	SF	APTRA		31	832	9	553	0	1,395
15# Asphalt Felt Underlayment					0.20	7.16	0.04	2.12	0.00	9.32
	15.00	CSF	ARFCA		3	107	1	32	0	140
Asphalt Shingles					1.20	43.00	0.27	44.52	0.00	87.79
	15.00	SQ	ARFCA		18	645	4	668	0	1,317
Alum. Drip Edge					0.01	0.48	0.01	0.20	0.00	0.68
	120.00	LF	MSHMA		2	57	1	24	0	82
Electrical Work on Outlets & Switches					0.28	11.00	0.04	2.12	0.00	13.16
	18.00	EA	EELEB		5	198	1	38	0	237
Electrical Work on Fire Alarm Pull Stations					0.82	32.50	0.11	2.12	0.00	34.73
	8.00	EA	EELEB		7	260	1	17	0	278
Electrical Work on Fire Alarm Bells					0.82	32.50	0.11	2.12	0.00	34.72
	4.00	EA	EELEB		3	130	0	8	0	139

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 16:21:08

PROJECT CB9011: CB BLDG 901, ECO #1 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 2

01. Contract

QUANTY UOM CREW ID		MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract		276	9,084	123	9,297	0	18,504
CB BLDG 901, ECO #1		276	9,084	123	9,297	0	18,504

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 16:21:08

PROJECT CB9011: CB BLDG 901, ECO #1 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

CARLISLE BARRACKS ENERGY STUDY
Individual Building Material Take Off Worksheet

Building No. 901		Building Name: GOLF HOUSE	
Date Prepared: 10 JAN, 94	Estimator: K. STICK	Sheet 3 of 4	
BID ITEM - INSUL. GL. / DBL. H. WINDOWS			
Description	Quantity	Unit Measurement	
DIV. 08 INSTALL 3/16" DS. THK. GLASS PANEL			
W/ FRAME ON THE FOLLOWING			
WINDOWS. (INSTALL PANEL ON AWNING			
WINDOWS WHERE INSECT SCREENS			
WOULD BE LOCATED)			
A. EXIST. 3'-6" x 5'-8" FIXED/AWNING - INSUL. GL.			
(NO WORK)	0		
B. EXIST. 4'-0" x 1'-10" AWNING - INSUL. GL.			
(NO WORK)	0		
C. EXIST. 3'-8" x 5'-4" FIXED - SINGLE GLAZING			
7 UNITS x 20 S.F. EA. = 140 S.F. OF			
INTERIOR INSTALLED PANEL	140	S.F.	
D. EXIST. 3'-8" x 1'-8" AWNING - SINGLE GLAZING			
10 UNITS x 6 S.F. EA. = 60 S.F. OF			
INTERIOR INSTALLED PANEL	60	S.F.	
E. EXIST. 2'-4" x 3'-10" DBL. HUNG - SINGLE GLAZING			
1 UNIT x 9 S.F. = 9 S.F. OF EXTERIOR			
DBL. HUNG STORM PANEL	1	EA.	
F. EXIST. 3'-2" x VARIES (SEE ELEV.) - SINGLE			
GLAZING. 224 S.F. TOTAL AREA OF			
INTERIOR INSTALLED PANELS	224	S.F.	

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9012: CB BLDG 901, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:31:02

TITLE PAGE 1

CB BLDG 901, ECO #2
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 901, Windows
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/13/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9012: CB BLDG 901, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:31:02

SETTINGS PAGE 1

** CONTRACTOR SETTINGS **

AMOUNT PCT PCT S RISK DIFF SIZE PERIOD INVEST ASSIST SUBCON

01 General Contractor

OVERHEAD	P	5.00								
HOME OFC	P	10.00								
PROFIT	C	8.65		0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00								

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9012: CB BLDG 901, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:31:02

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS	SUMMARY PAGE
PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3
DETAILED ESTIMATE	DETAIL PAGE
01. Contract.....	1

No Backup Reports...

* * * END TABLE OF CONTENTS * * *

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9012: CB BLDG 901, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 16:31:02

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	1,728	0	86	0	1,815	1814.74
CB BLDG 901, ECO #2	1.00 EA	1,728	0	86	0	1,815	1814.74

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9012: CB BLDG 901, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 16:31:02

SUMMARY PAGE 2

	QUANTITY UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00 EA	10	348	4	999	0	1,350	1350.18
CB BLDG 901, ECO #2 OVERHEAD	1.00 EA	10	348	4	999	0	1,350 68	1350.18
SUBTOTAL HOME OFC							1,418 142	
SUBTOTAL PROFIT							1,559 135	
SUBTOTAL BOND							1,694 34	
TOTAL INCL INDIRECTS CONTNGENCY							1,728 86	
TOTAL INCL OWNER COSTS							1,815	

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9012: CB BLDG 901, ECO #2 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 16:31:02

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	1,350	68	142	135	34	1,728	1728.32

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 16:31:02

PROJECT CB9012: CB BLDG 901, ECO #2 - ESOS Carlisle Barracks

DETAILED ESTIMATE

INTERIM SUBMISSION

DETAIL PAGE 1

01. Contract

	QUANTY UOM CREW ID	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract							
Single Glazing Installed on		0.02	0.79	0.01	2.23	0.00	3.02
Inside of Existing Windows	424.00 SF ACARB	9	335	3	944	0	1,282
Double Hung Storm Panel		0.36	12.70	0.13	55.12	0.00	67.95
	1.00 EA ACARB	0	13	0	55	0	68
Contract		10	348	4	999	0	1,350
CB BLDG 901, ECO #2		10	348	4	999	0	1,350

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 16:31:02

PROJECT CB9012: CB BLDG 901, ECO #2 - ESOS Carlisle Barracks

ERROR REPORT

INTERIM SUBMISSION

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *

[illegible]

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9013: CB BLDG 901, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:34:27

TITLE PAGE 1

CB BLDG 901, ECO #3
ESOS Carlisle Barracks
Contract No. DACA65-93-C-0018
Building 901, Caulk & W.S.
Carlisle Barracks, PA

Designed By: Benatec Associates
Estimated By: Benatec Associates

Prepared By: Benatec Associates

Date: 01/13/94

MCACES GOLD EDITION
Composer GOLD Copyright (C) 1985, 1988, 1990, 1992
by Building Systems Design, Inc.
Release 5.20J

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9013: CB BLDG 901, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TIME 16:34:27

SETTINGS PAGE 1

*** CONTRACTOR SETTINGS ***

		AMOUNT	PCT	PCT S	RISK	DIFF	SIZE	PERIOD	INVEST	ASSIST	SUBCON
01 General Contractor											
OVERHEAD	P	5.00									
HOME OFC	P	10.00									
PROFIT	C	8.65			0.052	0.075	0.119	0.052	0.075	0.120	0.118
BOND	P	2.00									

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 16:34:27

PROJECT CB9013: CB BLDG 901, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

TABLE OF CONTENTS

CONTENTS PAGE 1

SUMMARY REPORTS

SUMMARY PAGE

PROJECT OWNER SUMMARY - LEVEL 1.....	1
PROJECT DIRECT SUMMARY - LEVEL 1.....	2
CONTRACTOR INDIRECT SUMMARY.....	3

DETAILED ESTIMATE

DETAIL PAGE

01. Contract.....	1
-------------------	---

No Backup Reports...

*** END TABLE OF CONTENTS ***

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9013: CB BLDG 901, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT OWNER SUMMARY - LEVEL 1 **

TIME 16:34:27

SUMMARY PAGE 1

	QUANTITY UOM	CONTRACT	ESCALATN	CONTINGN	SIOH	TOTAL COST	UNIT COST
01 Contract	1.00 EA	3,041	0	152	0	3,193	3193.44
CB BLDG 901, ECO #3	1.00 EA	3,041	0	152	0	3,193	3193.44

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9013: CB BLDG 901, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** PROJECT DIRECT SUMMARY - LEVEL 1 **

TIME 16:34:27

SUMMARY PAGE 2

	QUANTITY	UOM	MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST	UNIT COST
01 Contract	1.00	EA	60	2,130	17	230	0	2,376	2375.95
CB BLDG 901, ECO #3 OVERHEAD	1.00	EA	60	2,130	17	230	0	2,376 119	2375.95
SUBTOTAL HOME OFC								2,495 249	
SUBTOTAL PROFIT								2,744 238	
SUBTOTAL BOND								2,982 60	
TOTAL INCL INDIRECTS CONTINGENCY								3,041 152	
TOTAL INCL OWNER COSTS								3,193	

Thu 13 Jan 1994

U.S. Army Corps of Engineers
PROJECT CB9013: CB BLDG 901, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION
** CONTRACTOR INDIRECT SUMMARY **

TIME 16:34:27

SUMMARY PAGE 3

	DIRECT	OVERHEAD	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
GC General Contractor	2,376	119	249	238	60	3,041	3041.37

Thu 13 Jan 1994

U.S. Army Corps of Engineers
 PROJECT CB9013: CB BLDG 901, ECO #3 - ESOS Carlisle Barracks
 INTERIM SUBMISSION
 01. Contract

TIME 16:34:27

DETAILED ESTIMATE

DETAIL PAGE 1

QUANTY UOM CREW ID		MANHRS	LABOR	EQUIPMNT	MATERIAL	OTHER	TOTAL COST
Contract							
Polyurethane Cmpd, 1/4"x1/4" Joint		4.65	166.39	1.03	9.54	0.00	176.96
on Ext. Doors & Windows	7.63 CLF ARFCA	35	1,270	8	73	0	1,350
Mtl Weatherstrip w/Neoprene Bulb		0.07	2.62	0.03	0.66	0.00	3.31
For Head and Jamb	165.00 LF ACARB	12	433	4	108	0	546
Mtl Weatherstrip for Door Bottom		0.21	7.50	0.08	0.85	0.00	8.42
Surface Mounted w/Vinyl Bulb	57.00 LF ACARB	12	427	4	48	0	480
Bulb							
Contract		60	2,130	17	230	0	2,376
CB BLDG 901, ECO #3		60	2,130	17	230	0	2,376

Thu 13 Jan 1994

U.S. Army Corps of Engineers

TIME 16:34:27

PROJECT CB9013: CB BLDG 901, ECO #3 - ESOS Carlisle Barracks
INTERIM SUBMISSION

ERROR REPORT

ERROR PAGE 1

No errors detected...

* * * END OF ERROR REPORT * * *